

Auditing Agency – Prathamesh Energy Solution, A-302, Shiv Unnati Residency, Kalepadal, Hadapsar Pune- 411 028

Prathamesh Energy Solution

A-302, Shiv Unnati residency, Kalepadal, Hadapsar, Pune-411028

Ref: PES/BVCOEL/2023-24/52

Date: 07/02/2024

To,

The Principal Bharati Vidyapeeth's College of Engineering, Lavale, Pune

Sub: Submission of Report on Energy Audit of College Campus

Respected Sir,

Please find enclosed herewith the report

Thanking you Yours faithfully

For Prathamesh Energy Solution

Authorized Signatory

Prathamesh Energy Solution

A-302, Shiv Unnati Residency, Kalepadal, Hadapsar, Pune 411028

Ref: EC/BVCoEL/23-24/53

CERTIFICATE

This is to certify that we have conducted Energy Audit at **Bharati Vidyapeeth's College of Engineering, Lavale, Pune**, in the Academic year 2023-24


.The College has adopted following Energy Efficient and best practices:

- Usage of Energy Efficient LED Fittings
- Maximum usage of Day Lighting
- Installed APFC of 270KVAr
- Green Campus
- Rain water Harvesting system

We appreciate the support of Management, involvement of faculty members and students in the process of making the Campus Energy Efficient.

For,

Prathamesh Energy Solution,



| Sr. No | Particulars | Page No |
|--------|--|---------|
| I | Acknowledgement | 6 |
| П | Executive Summary | 7 |
| Ш | Abbreviations | 9 |
| | | |
| 1 | Introduction | 10 |
| 2 | Study of Connected Load | 11 |
| 3 | Historical Data Analysis- Electrical Energy | 13 |
| 4 | Carbon foot printing | 16 |
| 5 | Electrical Measurements | 19 |
| 6 | Scope of renewable energy and efficient facility at college campus | 27 |
| 8 | Suggestions and Recommendations | 31 |

INDEX

ACKNOWLEDGEMENT

We at Prathamesh Energy Solution, Pune, express our sincere gratitude to the management and Principal of Bharati Vidyapeeth's College of Engineering, Lavale, Pune for awarding us the assignment of Energy Audit of their College campus located at Lavale, Pune.

We are very much thankful to

- Dr. Vishwajeet Kadam, Secretary Bharati Vidyapeeth, Pune
- Dr. Shivajirao Kadam, Chancellor, Bharati Vidyapeeth Deemed to be University.
- Dr. K D Jadhav, Jt. Secretary (Admin), bharati Vidyapeeth, Pune
- Dr. R N Patil, Principal, Bharati Vidyapeeth's College of Engineering, Lavale, Pune

for giving us opportunity to conduct detailed energy audit of the institute and provide all the required data and information promptly for the smooth conduction of detailed energy and green audit.

We are also thankful to various Heads of Departments, IQAC Coordinator & other Staff members for helping us during the survey and field visit.

We are also thankful to all the technical staff and office staff for helping during the field visit and measurements at the college campus.

EXECUTIVE SUMMARY

After the Field measurements & analysis, we present herewith important observations made and various measures to reduce the Energy Consumption & mitigate the CO₂ emissions

1. Bharati Vidyapeeth's College of Engineering, Lavale, Pune, consumes electrical Energy in majority used for various gadgets & office operations.

2. The various projects already implemented by the College are

- > Installed APFC of 270 kVAR at Main electrical distribution to maintain Power factor.
- > Usage of natural day lights and natural air circulation
- > Usage of Natural Day light in corridors specifically
- > Usage of LED lighting for Admin & outdoor lighting
- > Initiatives for water conservation through STP at the campus

3. Important Parameters: Electrical Energy:

Electricity is used for different purposes and at different sections in the college campus. The details of electricity distribution as mentioned below.

| Sr. No. | Consumer No. | Electrical Meter No. | Location/Purpose | Payee |
|------------|-----------------|-------------------------|---|--|
| 1 | 182829055190 | 076- 05040425 | College building/building operation | M/S. Joint Secretary Bharati Vidyapeeth College of Engineering, Lavale |

The important parameters of electrical consumption as per Consumer no. in the campus are mentioned as below.

| Sr. No | Consumer No. | Parameter | Max | Min | Average |
|-----------|---------------|-------------------------|--------|--------|-----------|
| 1 | 4 40000055400 | Units consumed, kVAh | 26246 | 14403 | 18447.33 |
| | 182829055190 | Electricity Bill amount | 516876 | 347361 | 406580.3 |
| | | Total | | | 425027.63 |

4. Important Parameters: CO₂ Emissions (Average, MT/Annum)

| | Consumer No. | | Value |
|----|--------------|--|--------|
| No | | Particulars | МТ |
| 1 | 182829055190 | CO ₂ - Emissions- Electricity Usage | 177.09 |
| | | Total | 177.09 |

On the basis of average electricity consumption CO_2 emission is 177.09 MT /annum. In addition to this LPG is being consumed for canteen for food preparation. Nearly LPG consumption annually is 12 commercial cylinders i.e. 228 kg/annum. On the basis of average LPG usage CO_2 emission is 0.68MT/annum.

5. Benchmark: In terms of Electrical Energy & CO₂ emissions:

We now present two important benchmarks in respect of Electrical Energy consumption & CO₂ emissions as under.

| No | Particulars | Value | Unit |
|----|-----------------------------|-------|-----------------------|
| 1 | Electrical Energy consumed | 2.44 | kWh/sq. ft. |
| 3 | CO ₂ - Emissions | 1.01 | Kg per annum /sq. ft. |

6. Recommendations:

We present herewith various proposals to reduce the Electrical Energy demand and reduce the CO_2 emissions

| S. No. | Recommendation | Annual saving potential in kWh /Kg of LPG | Annual Saving Potential in MT of CO ₂ | Annual monetary gain, Rs. |
|-----------|---|---|---|---------------------------------|
| 1 | Installation of 50kW Solar PV roof top on college building | 84000 kWh | 67.2 | 840000 |
| 2 | Solar street lights | 262.8 kWh | 0.21 | 2628 |
| 3 | Solar powered light for hoarding | - | - | - |
| 4 | Solar charging stations | - | - | - |
| | Total | 84262.8 | 67.41 | 842628 |

Notes & assumptions:

- 1. 1 Unit of Electrical Energy releases 0.8 Kg of CO₂ into atmosphere
- 2. 1 Kg of LPG releases 3 Kg of CO₂ into atmosphere
- 3. Daily working hours-10
- 4. Annual working Days-280
- 5. Average Rate of Electrical Energy- Rs 10 per kWh

2023-24

ABBREVIATIONS

| DP | : | Double Pole |
|--------|---|---|
| CFL | : | Compact Fluorescent Lamp |
| EESL | : | Energy Efficiency Services Limited |
| FΡ | : | Feeder Pillar |
| MSEDCL | : | Maharashtra State Electricity Distribution Company Ltd. |
| MEDA | : | Maharashtra Energy Development Agency |
| MIDC | : | Maharashtra Industrial Development Corporation |
| V | : | Voltage |
| I | : | Current |
| kW | : | kilo-Watt |
| kVA | : | Apparent Power |
| kVAr | : | Reactive Power |
| ΡF | : | Power Factor |
| kWp | : | Kilo Watt peak |

CHAPTER-I ENERGY AUDIT: INTRODUCTION

1.1 Objectives:

- 1. To study present level of Energy Consumption
- 2. To Study the present CO₂ emissions
- 3. To assess the various equipment/facilities from Energy efficiency aspect
- 4. To measure various Electrical parameters
- 5. To study Scope for usage of Renewable Energy
- 6. To study various measures to reduce the Energy Consumption

1.2 Audit Methodology:

- 1. Study of connected load
- 2. Study of various Electrical parameters
- 3. To prepare the Report with various ENCON measures with payback analysis

1.3 Energy Audit Instruments:

- 1. Portable Power Analyzer
- 2. Lux meter
- 3. Anemometer
- 4. Digital Temperature Indicator
- 5. CO₂ Meter
- 6. Water TDS meter

1.4 General Details of Bharati Vidyapeeth's College of Engineering, Lavale, Pune:

| No | Head | Particulars | | |
|----|-----------------------|---|--|--|
| 1 | Name of Institution | Bharati Vidyapeeth's College of Engineering | | |
| 2 | Address | Lavale, Pune | | |
| 3 | Year of Establishment | 2012 | | |
| 4 | Salient Features | Affiliated to Savitribai Phule Pune University | | |
| 4 | Courses offered | UG in Civil, Computer, E&TC and Mechanical Engineering | | |
| 5 | No of Students | 654 | | |
| 6 | Total built up area | 173695 Sq. ft. | | |


CHAPTER-II STUDY OF CONNECTED LOAD

In this chapter, we present the details of various Electrical loads as under

2.1 Study of Fitting wise Connected Load:

| Sr. No. | Name of Appliance | Wattage/unit (approx.) | Quantity (approx.) | Total Wattage (approx.) |
|------------|-------------------|---------------------------|-----------------------|----------------------------|
| 1 | Fan | 60 | 464 | 27.84 |
| 2 | Tubelight 1 | 24 | 493 | 11.83 |
| | Tubelight 2 | 40 | 523 | 20.92 |
| 3 | Bulb | 18 | 60 | 1.08 |
| 4 | Desktop | 18 | 375 | 6.75 |
| 5 | Printer | 360 | 22 | 7.92 |
| 6 | AC | 1650 | 05 | 8.25 |
| 7 | Water cooler | 300 | 05 | 1.5 |
| 8 | LED street lights | 90 | 38 | 3.42 |
| 10 | Canteen Load | All | - | 2.98 |
| 11 | Motor | All | 16 | 90.76 |
| 14 | Water Heater | 3000 | 24 | 72.00 |
| 15 | PICT Board | 100 | 6 | 0.60 |
| 16 | AC Under Wall | 1050 | 17 | 17.85 |
| | Total | | | 245.87 |

We present the same in a PIE Chart as under



CHAPTER-III HISTORICAL DATA ANALYSIS: ELECTRICAL ENERGY


In this chapter, we present the analysis of last year Electricity Bills

3.1 Consumer No. 182829055190

This consumer is the major contributors for billing in the Bharati Vidyapeeth's College of Engineering, Lavale campus, Pune. BV's College of Engineering, building load is connected to the same meter. Monthly consumption for last few months and bill amount is as follows.

| Sr. | | | Demand | |
|-----|------------|----------|--------|----------|
| No | Month | kVAh | | Amount |
| 1 | Nov-2023 | 14785 | 322 | 368958 |
| 2 | Oct-2023 | 20795 | 322 | 449042 |
| 3 | Sep-2023 | 18412 | 322 | 415571 |
| 4 | Aug-2023 | 15822 | 322 | 374885 |
| 5 | July-2023 | 14403 | 322 | 355560 |
| 6 | June-2023 | 21338 | 322 | 450002 |
| 7 | May-2023 | 26246 | 322 | 516876 |
| 8 | April-2023 | 20323 | 322 | 441108 |
| 9 | March-2023 | 19238 | 299 | 407576 |
| 10 | Feb-2023 | 15298 | 299 | 347361 |
| 11 | Jan-2023 | 16631 | 299 | 366146 |
| 12 | Dec-2022 | 18077 | 299 | 385878 |
| 13 | Total | 221368 | | 4878963 |
| 14 | Average | 18447.33 | | 406580.3 |
| 15 | Max | 26246 | | 516876 |
| 16 | Min | 14403 | | 347361 |

Table No. 1: Electrical Bill Analysis- 2023-24: 182829055190



111.23

Jun 23

Months

Mayi23

APT-23

AUBS23

Seb. J.S

404.23

002-23

To study the variation of Monthly Units' Consumption: 3.1.1

3.1.2 To study the variation of Demand

teb.23

Mar.23

Jan 23

30000

25000

20000

15000


10000

5000


0

Decili

Monthly Unit Consumption, kVAh



3.1.3 To study the variation of Monthly Electricity Bill:



3.2 Summary:

| Sr. No. | Consumer No. | Annual Electricity Consumption, kVAh | Annual Bill, Rs |
|------------|--------------|---|-----------------|
| 1 | 182829055190 | 221368 | 4878963 |

3.3 Key Inference drawn:

From the above analysis, we present following important parameters:

| Sr. No | Consumer No. | Parameter | Мах | Min | Average |
|-----------|---------------|-------------------------|--------|--------|-----------|
| 1 | 4 40000055400 | Units consumed, kVAh | 26246 | 14403 | 18447.33 |
| | 182829055190 | Electricity Bill amount | 516876 | 347361 | 406580.3 |
| | | Total | | | 425027.63 |

3.4 Benchmarking: Now we compute the Electrical Energy Consumed per square feet of the College Building as under

| No | Parameter | Value | Unit |
|----|-----------------------|-----------|--------------|
| 1 | Units consumed, kVAh | 425027.63 | kVAh |
| 2 | College area | 173695 | Sq. ft. |
| 3 | Unit consumed/sq. ft. | 2.44 | kVAh/sq. ft. |

CHAPTER-IV CARBON FOOTPRINTING

A Carbon Foot print is defined as the Total Greenhouse Gas emissions, emitted due to various activities.

In this we compute the emissions of Carbon-Di-Oxide, by usage of the various forms of Energy used by the College for performing its day to day activities. The college uses electrical energy for operating various electrical gadgets.

We herewith furnish the details of electrical Energy consumption consumer number wise as under

4.1 Month wise Consumption of Electrical Energy: 182829055190

| Sr. No | Month | kVAh |
|--------|------------|----------|
| 1 | Nov-2023 | 14785 |
| 2 | Oct-2023 | 20795 |
| 3 | Sep-2023 | 18412 |
| 4 | Aug-2023 | 15822 |
| 5 | July-2023 | 14403 |
| 6 | June-2023 | 21338 |
| 7 | May-2023 | 26246 |
| 8 | April-2023 | 20323 |
| 9 | March-2023 | 19238 |
| 10 | Feb-2023 | 15298 |
| 11 | Jan-2023 | 16631 |
| 12 | Dec-2022 | 18077 |
| 13 | Total | 221368 |
| 14 | Average | 18447.33 |
| 15 | Max | 26246 |
| 16 | Min | 14403 |

4.2 Basis for computation of CO₂ Emissions:

The basis of Calculation for CO₂ emissions due to Electrical Energy are as under


• 1 Unit (kWh) of Electrical Energy releases 0.8 Kg of CO2 into atmosphere

Based on the above Data we compute the CO_2 emissions which are being released in to the atmosphere by the College due to its Day to Day operations.

4.3 Month wise CO2 Emissions: 182829055190

| Sr. No | Month | Electrical Energy Consumed, kVAh | CO2 Emissions due to Electricity, MT |
|--------|------------|-------------------------------------|---|
| 1 | Nov-2023 | 14785 | 11.83 |
| 2 | Oct-2023 | 20795 | 16.64 |
| 3 | Sep-2023 | 18412 | 14.73 |
| 4 | Aug-2023 | 15822 | 12.66 |
| 5 | July-2023 | 14403 | 11.52 |
| 6 | June-2023 | 21338 | 17.07 |
| 7 | May-2023 | 26246 | 21.00 |
| 8 | April-2023 | 20323 | 16.26 |
| 9 | March-2023 | 19238 | 15.39 |
| 10 | Feb-2023 | 15298 | 12.24 |
| 11 | Jan-2023 | 16631 | 13.30 |
| 12 | Dec-2022 | 18077 | 14.46 |
| 13 | Total | 221368 | 177.09 |
| 14 | Average | 18447.33 | 14.76 |
| 15 | Max | 26246 | 21.00 |
| 16 | Min | 14403 | 11.52 |

4.4 Representation of Month wise CO₂ emissions:



4.5 Benchmarking:

Now we compute the CO2 emissions per sq. ft. basis as under:

| No | Parameter | Value | Unit |
|----|-----------------------|--------|--------------------------------|
| 1 | CO2 emissions | 177.09 | MT/annum |
| 2 | College area | 173695 | Sq. ft. |
| 3 | CO2 emissions/sq. ft. | 1.01 | Kg of CO₂ per annum/sq. ft. |

CHAPTER-V ELECTRICAL MEASUREMENTS

In this Chapter, we present the details of measurements at the distribution center and main meter room.

5.1 Measurement at Main Incomer feeder:

With the help of power analyzer various electrical parameters like voltage, current, KW and PF are measured. The sample extract of measured data is as follows.

| Recording | | | | | | | | | | | | | | | | |
|----------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-------|-----------|-------|------------|------------|------------|------------|------------|------------|
| Date: | V1 rms | V2 rms | V3 rms | A1 rms | A2 rms | A3 rms | AN rms | F | PT (W) | PFT | V1 THDf | V2 THDf | V3 THDf | A1 THDf | A2 THDf | A3 THDf |
| | V | V | V | A | A | A | A | Hz | W | | % f | % f | % f | % f | % f | % f |
| 05-02- 2024 | 246.1 | 247.4 | 246.2 | 65 | 34.6 | 34.8 | 31.1 | 50.04 | 32988 | 0.994 | 1 | 1.1 | 0.9 | 6.2 | 10.9 | 11.1 |
| 05-02- 2024 | 245.9 | 247 | 245.9 | 64.8 | 47.2 | 35.6 | 24.6 | 50.01 | 36219 | 0.995 | 1 | 1.1 | 0.9 | 6.2 | 8.6 | 11.2 |
| 05-02- 2024 | 246.7 | 247.5 | 246.7 | 64.8 | 47.9 | 35.7 | 24.3 | 50.03 | 36545 | 0.995 | 0.9 | 1.1 | 0.8 | 6.2 | 8.4 | 11 |
| 05-02- 2024 | 246.7 | 247.6 | 246.5 | 60.8 | 35.6 | 35.9 | 26.3 | 50.03 | 32519 | 0.994 | 0.9 | 1.1 | 0.8 | 6.9 | 10.7 | 11 |
| 05-02- 2024 | 246.3 | 247.2 | 246 | 53.2 | 35.2 | 35.3 | 20.1 | 50.03 | 30334 | 0.993 | 1 | 1.1 | 0.9 | 8.3 | 10.6 | 11.2 |
| 05-02- 2024 | 246.1 | 247 | 245.8 | 52.6 | 34.4 | 35 | 21 | 50.03 | 29884 | 0.993 | 0.9 | 1.1 | 0.8 | 8.8 | 10.7 | 11.2 |
| 05-02- 2024 | 246 | 246.9 | 245.8 | 40.1 | 33.6 | 34.7 | 12.8 | 50.02 | 26477 | 0.99 | 1 | 1 | 0.8 | 11.8 | 10.8 | 11.2 |
| 05-02- 2024 | 245.8 | 246.5 | 245.4 | 39.2 | 33.8 | 35 | 12.4 | 50.01 | 26328 | 0.99 | 1 | 1.1 | 0.8 | 11.9 | 10.7 | 11.2 |
| 05-02- 2024 | 245.8 | 246.6 | 245.5 | 39.3 | 34.2 | 35.5 | 12.8 | 50 | 26582 | 0.99 | 0.9 | 1 | 0.8 | 11.8 | 10.4 | 11 |
| 05-02- 2024 | 245.4 | 246.1 | 245.1 | 41.9 | 37.4 | 39 | 13.7 | 50 | 28536 | 0.983 | 0.8 | 1 | 0.8 | 11.2 | 9.7 | 10.5 |
| 05-02- 2024 | 245.3 | 246.3 | 245.1 | 48.3 | 44.2 | 44.4 | 12.8 | 50 | 33119 | 0.985 | 0.9 | 1 | 0.9 | 10.4 | 9.3 | 9.7 |
| 05-02- 2024 | 245.3 | 246.4 | 245.2 | 65.7 | 50.2 | 49.6 | 19.6 | 50.02 | 40440 | 0.993 | 1 | 1.1 | 1 | 7.9 | 9.4 | 9.4 |
| 05-02- 2024 | 245 | 246.1 | 244.8 | 66.6 | 49.4 | 49 | 21.7 | 50.02 | 40229 | 0.993 | 1 | 1.1 | 1 | 7.9 | 9.5 | 9.6 |
| 05-02- 2024 | 244.9 | 245.8 | 244.6 | 45.9 | 40.5 | 40.7 | 12.7 | 50.02 | 30842 | 0.988 | 1 | 1.1 | 0.9 | 11.3 | 9.9 | 10.7 |
| 05-02- 2024 | 245 | 245.7 | 244.7 | 39.4 | 34.3 | 33.8 | 11 | 50.02 | 26169 | 0.991 | 0.9 | 1 | 0.8 | 12.1 | 9.8 | 11.7 |
| 05-02- 2024 | 244.6 | 245.4 | 244.3 | 39.6 | 34.2 | 33.9 | 11.1 | 50.03 | 26162 | 0.991 | 0.9 | 1 | 0.8 | 12.1 | 9.8 | 11.6 |
| 05-02- 2024 | 244 | 244.7 | 243.7 | 39.7 | 34.2 | 33.7 | 10.9 | 50.02 | 26095 | 0.991 | 0.9 | 1 | 0.8 | 12.1 | 9.7 | 11.7 |
| 05-02- 2024 | 244.3 | 245.2 | 244.1 | 49.3 | 33.9 | 33.7 | 18 | 50.02 | 28423 | 0.993 | 0.8 | 1 | 0.7 | 9.7 | 10 | 11.6 |
| 05-02- 2024 | 244.1 | 245.2 | 243.9 | 52.2 | 33.6 | 32 | 21.1 | 50.01 | 28645 | 0.993 | 0.9 | 1 | 0.8 | 8.9 | 9.8 | 12.3 |
| 05-02- 2024 | 243.9 | 244.8 | 243.6 | 52 | 33.3 | 30.1 | 21.8 | 50.03 | 28018 | 0.993 | 0.9 | 1.1 | 0.9 | 9 | 9.8 | 13.4 |
| 05-02- | 244.1 | 244.9 | 244 | 51.8 | 37.5 | 30 | 20.2 | 50.03 | 29026 | 0.993 | 1 | 1.2 | 0.9 | 9.1 | 9.2 | 13.4 |

Prathamesh Energy Solution, Pune

| 2024 | | | | | | | | | | | | | | | | |
|----------------|-------|-------|-------|------|------|------|------|-------|-------|-------|-----|-----|-----|------|------|------|
| 05-02- 2024 | 244.1 | 244.9 | 244 | 48.3 | 38.7 | 26.8 | 17.8 | 50.02 | 27304 | 0.98 | 1 | 1.2 | 1 | 9.7 | 8.6 | 15.3 |
| 05-02- 2024 | 244.7 | 245.7 | 244.6 | 40.9 | 29.2 | 24.7 | 16.3 | 50.01 | 22418 | 0.962 | 1 | 1.1 | 0.9 | 11.6 | 12 | 16.9 |
| 05-02- 2024 | 244.3 | 245.2 | 244.1 | 47.5 | 37.5 | 32.5 | 15.3 | 50 | 28489 | 0.99 | 0.9 | 1 | 0.8 | 9.7 | 9 | 12.5 |
| 05-02- 2024 | 243.9 | 244.8 | 243.7 | 59.8 | 42.6 | 37.4 | 21.5 | 50 | 33903 | 0.991 | 1 | 1.1 | 0.8 | 6.9 | 8.5 | 10.6 |
| 05-02-2024 | 243.2 | 244.2 | 243.2 | 54.9 | 38.1 | 32.6 | 20.9 | 50.01 | 30378 | 0.992 | 1 | 1.1 | 0.9 | 8.1 | 9.5 | 12.1 |
| 05-02- 2024 | 243.7 | 244.7 | 243.6 | 46.3 | 30.5 | 25.2 | 19.2 | 50.03 | 24319 | 0.975 | 1 | 1.1 | 0.9 | 10.3 | 12 | 15.3 |
| 05-02- 2024 | 244.1 | 245 | 244.1 | 42.9 | 28.8 | 23.8 | 17.6 | 50.02 | 22682 | 0.97 | 1.1 | 1.2 | 0.9 | 11.1 | 12.8 | 16.1 |
| 05-02- 2024 | 244.8 | 245.7 | 244.8 | 43.4 | 28.5 | 23.9 | 18.5 | 50.02 | 22815 | 0.97 | 1 | 1.1 | 0.8 | 10.7 | 13.1 | 16.1 |
| 05-02-2024 | 244.3 | 245.2 | 244.2 | 47.7 | 33.1 | 28.5 | 19 | 50.01 | 26487 | 0.988 | 1 | 1.1 | 0.9 | 9.4 | 11.1 | 13.5 |
| 05-02- 2024 | 244.3 | 245.2 | 244.1 | 49 | 34.2 | 33.4 | 19.9 | 50.03 | 28332 | 0.992 | 1 | 1.1 | 0.9 | 9.2 | 10.5 | 12.1 |
| 05-02- 2024 | 244.7 | 245.7 | 244.6 | 49 | 34.4 | 34.4 | 20.1 | 50.05 | 28692 | 0.992 | 1 | 1.1 | 0.8 | 9.3 | 10.4 | 11.8 |
| 05-02- 2024 | 244.7 | 245.9 | 244.8 | 52.8 | 40.2 | 30.4 | 21.1 | 50.04 | 30119 | 0.993 | 1 | 1.1 | 0.8 | 8.8 | 9.2 | 12.2 |
| 05-02- 2024 | 244.7 | 245.8 | 244.8 | 50.3 | 44.5 | 30.9 | 19.5 | 50.03 | 30674 | 0.993 | 0.9 | 1.1 | 0.8 | 9.8 | 8.6 | 12 |
| 05-02- 2024 | 244.5 | 245.3 | 244.4 | 48.7 | 49.5 | 37.9 | 13.5 | 50.04 | 32956 | 0.989 | 0.9 | 1.1 | 0.8 | 10.6 | 8.2 | 10.6 |
| 05-02- 2024 | 244.9 | 245.9 | 244.9 | 59.1 | 60.1 | 56.1 | 1 | 50.09 | 42843 | 0.995 | 1 | 1.1 | 0.9 | 9.2 | 7.8 | 7.7 |
| 05-02- 2024 | 244.8 | 245.7 | 244.7 | 57.1 | 52.6 | 55.6 | 8 | 50.1 | 40336 | 0.995 | 1 | 1.1 | 0.9 | 9.2 | 8.9 | 7.4 |
| 05-02- 2024 | 244.2 | 245.1 | 244 | 47.9 | 40 | 42.9 | 14.7 | 50.09 | 31742 | 0.991 | 0.9 | 1 | 0.8 | 10.7 | 9.8 | 9.5 |
| 05-02- 2024 | 244.5 | 245.5 | 244.3 | 44 | 36.3 | 41.9 | 15.2 | 50.07 | 29697 | 0.99 | 0.9 | 1 | 0.8 | 11.3 | 9.8 | 9.8 |
| 05-02- 2024 | 244.6 | 245.5 | 244.4 | 43.5 | 36.9 | 41.8 | 14.6 | 50.05 | 29666 | 0.99 | 1 | 1.1 | 0.9 | 11.5 | 9.7 | 9.9 |
| 05-02- 2024 | 244.1 | 244.9 | 243.7 | 43.4 | 36.8 | 41.8 | 14.7 | 50.04 | 29556 | 0.99 | 1 | 1.1 | 0.9 | 11.5 | 9.8 | 10 |
| 05-02- 2024 | 243.5 | 244.4 | 243.1 | 41.1 | 32.9 | 39.2 | 15.9 | 50.02 | 27297 | 0.987 | 1.1 | 1.2 | 0.9 | 12.3 | 10.8 | 10.9 |
| 05-02- 2024 | 243.7 | 244.7 | 243.4 | 42 | 33.3 | 39.8 | 17.2 | 50.01 | 27676 | 0.985 | 1 | 1.1 | 0.8 | 11.7 | 10.5 | 10.9 |
| 05-02- 2024 | 243.6 | 244.5 | 243.3 | 42.6 | 34.3 | 39.9 | 16.1 | 50.01 | 28262 | 0.991 | 1 | 1.1 | 0.8 | 11.5 | 10 | 10.5 |
| 05-02- 2024 | 243.2 | 244 | 242.9 | 40.3 | 34.7 | 37.6 | 13.1 | 50.02 | 27112 | 0.988 | 0.9 | 1 | 0.8 | 11.8 | 10.1 | 11.2 |
| 05-02- 2024 | 243.3 | 244.1 | 243 | 36.2 | 43.1 | 35.6 | 4.3 | 50.03 | 27594 | 0.985 | 1 | 1.1 | 0.8 | 12.8 | 8.2 | 11.8 |
| 05-02- 2024 | 243.1 | 243.9 | 242.8 | 36.4 | 48.4 | 41.3 | 7.7 | 50.02 | 30273 | 0.986 | 1 | 1.1 | 0.9 | 12.3 | 7.8 | 10.1 |
| 05-02- 2024 | 241.6 | 242.3 | 241.1 | 45.2 | 57.8 | 49.6 | 11.7 | 49.97 | 36459 | 0.987 | 1.1 | 1.1 | 0.9 | 10.5 | 7.3 | 9.4 |
| 05-02- 2024 | 241.3 | 242 | 240.8 | 46.1 | 58.5 | 50.2 | 11.4 | 49.94 | 36980 | 0.988 | 1.1 | 1.1 | 0.9 | 10.5 | 7.5 | 9.2 |
| 05-02- 2024 | 241.2 | 242 | 240.7 | 47.1 | 49.3 | 48.3 | 12.8 | 49.94 | 34623 | 0.989 | 1.1 | 1.1 | 0.9 | 11.2 | 10.1 | 9.7 |
| 05-02- | 241.4 | 242.2 | 240.9 | 41.7 | 41.2 | 42.6 | 12.7 | 49.95 | 30030 | 0.989 | 1.1 | 1.1 | 0.9 | 11.7 | 10.8 | 9.8 |

| 5.6.02 241.9 242.8 241.6 35.6 36.2 38.3 12.2 49.98 26354 0.987 1 1 0.8 12.6 10.5 10 05-02- 2024 241.5 242.3 241.2 23.3 34.5 36.5 12 50.02 24950 0.987 1 1 0.8 13 10.2 9.7 05-02- 2024 241.4 242.3 241.1 33.4 32.3 36.7 13.2 50.03 24482 0.988 1 1.1 0.8 12.9 10.9 9.7 05-02 241.8 241.0 240.6 0.8 31.1 37.1 15.4 49.98 2392 0.986 1.1 1.1 0.9 14.6 12.2 10.2 05-02 240.8 241.6 240.4 29 31.3 37.1 15.1 49.99 2321 0.98 1.1 1.1 0.9 14.9 12.5 10.3 05-02 241.1 241 | 2024 | | | | | | | | | | | | | | [| | |
|---|--------|--------|-------|-------|------|------|------|------|----------------|--------|----------|-----|-----|-----|------|------|------|
| 05:02. 241.5 242.3 241.2 33.3 34.5 36.5 12 50.02 24990 0.987 1 1 0.8 13 10.2 9.7 05:02- 2024 241.4 242.3 24.1.1 33.4 32.3 36.7 13.2 50.013 24482 0.988 1 1.1 0.8 13.8 11.5 9.6 05:02- 2024 241.8 24.6 241.4 32.5 30.4 36.7 14.7 50.03 2824 0.87 1.1 1.1 0.9 1.4 11.9 10 05:02- 2024 241.9 240.7 28.9 30.9 36.4 14 49.99 2321 0.986 1.1 1.1 0.8 1.4.6 12.2 10.2 05:02- 2024 241.6 240.4 29 31.3 37.1 15.4 90.92 2321 0.98 1.1 1.1 0.8 1.5.1 12.6 10.2 05:02- 2024 241.1 241.8 240.7 | | 241.9 | 242.8 | 241.6 | 35.6 | 36.2 | 38.3 | 12.2 | 49.98 | 26354 | 0.987 | 1 | 1 | 0.8 | 12.6 | 10.5 | 10 |
| 2024 241.4 242.3 241.1 33.4 32.3 36.7 1.2 50.03 24482 0.98 1 1.1 0.8 1.29 10.9 9.7 2024 241.8 242.6 241.4 32.5 30.4 36.7 1.42 50.03 24842 0.98 1.1 1.1 0.9 1.4 1.1 9.6 2024 241.9 240.6 30.8 31.3 37.1 15.4 49.99 2321 0.86 1.1 1.0 0.9 1.46 1.2 10.1 05:02 240.8 241.6 240.4 29 3 37.1 15.1 49.99 2321 0.986 1.1 1.0 0.9 1.46 1.2 10.1 0.02 2.41 240.6 240.4 29 3.3 37.1 15.4 49.99 2321 0.988 1.1 1.4 0.9 15.1 12.0 10.1 05:02 241.1 241.2 240.4 29.1 | - | | | | | | | | | | . | | | | 10 | 10.0 | |
| 05:02- 0204 241.4 242.3 241.1 33.4 32.3 36.7 13.2 50.03 24482 0.988 1 1.1 0.8 12.9 10.9 9.7 05:02- 0204 241.8 242.6 241.4 32.5 30.4 36.7 14.7 50.03 23824 0.987 1.1 1.1 0.9 1.8 11.5 9.6 05:02 2024 241.9 240.7 28.9 30.9 36.4 14 49.99 22921 0.986 1.1 1.1 0.9 14.6 12.2 10.2 05:02- 2024 240.8 241.5 240.3 28.7 31.3 37.1 15.1 49.95 23023 0.982 1.1 1.1 0.8 15.1 12.2 10.1 05:02- 2024 241.6 240.4 29 31.3 38.3 16.4 49.98 23321 0.98 1.1 1.1 0.8 15.1 12.6 10.2 05:02- 2024 241.1 241.6 | | 241.5 | 242.3 | 241.2 | 33.3 | 34.5 | 36.5 | 12 | 50.02 | 24950 | 0.987 | 1 | 1 | 0.8 | 13 | 10.2 | 9.7 |
| 05-02- 0204 241.8 242.6 21.4 32.5 30.4 36.7 14.7 50.03 23824 0.987 1.1 1.1 0.9 15.8 11.5 9.6 05-02- 0204 241 241.9 240.6 30.8 31.1 37.1 14.2 49.98 25592 0.986 1.1 1 0.9 14.6 12.2 10.2 05-02- 2024 241.0 241.0 240.4 29 31.3 37.1 15.4 49.97 23116 0.988 1 1 0.8 14.6 12.2 10.2 05-02- 2024 241.8 240.5 29.2 32.7 15.4 49.98 2321 0.98 1 1 0.8 15.1 12.6 10.2 05-02- 2024 241.1 241.8 240.5 29.2 32.7 15.4 50 23461 0.982 1.1 1.1 0.9 15.1 12.6 10.2 05-02- 2024 241.1 241.8 240.2 <t< td=""><td></td><td>241.4</td><td>242.3</td><td>241.1</td><td>33.4</td><td>32.3</td><td>36.7</td><td>13.2</td><td>50.03</td><td>24482</td><td>0.988</td><td>1</td><td>1.1</td><td>0.8</td><td>12.9</td><td>10.9</td><td>9.7</td></t<> | | 241.4 | 242.3 | 241.1 | 33.4 | 32.3 | 36.7 | 13.2 | 50.03 | 24482 | 0.988 | 1 | 1.1 | 0.8 | 12.9 | 10.9 | 9.7 |
| 2024 241 241.9 240.9 240.9 240.9 240.9 240.9 240.9 14 1.0 < | | 241.9 | 242.6 | 241.4 | 22.5 | 20.4 | 267 | 147 | 50.02 | 22824 | 0.097 | 1 1 | 11 | 0.0 | 12.9 | 11.5 | 0.6 |
| 2024 A | | 241.0 | 242.0 | 241.4 | 32.3 | 30.4 | 30.7 | 14.7 | 50.05 | 23624 | 0.967 | 1.1 | 1.1 | 0.9 | 13.0 | 11.5 | 9.0 |
| 05:02- 0204 241.2 241.2 241.7 240.7 28.9 30.9 36.4 14 49.99 22221 0.986 1.1 1.1 0.9 1.4.6 12.2 10.1 05:02- 2024 240.8 241.5 240.3 28.7 31.3 37.3 15. 49.97 23116 0.983 1.1 1.1 0.9 14.6 12.4 10.1 05:02- 2024 241.1 241.6 240.4 29 31.3 38.3 16.4 49.98 2321 0.98 1.1 1.1 0.9 15.1 12.6 10.2 05:02- 2024 241.1 241.2 240.7 29.1 31.2 35.6 13.9 50 22987 0.983 1.1 1.1 0.9 15.1 13.2 10.6 05:402- 2024 241.1 242.6 240.2 241.3 35.2 35.6 15.5 49.97 2314 0.985 1.1 1.2 1.9 15.1 13.2 10.6 | | 241 | 241.9 | 240.6 | 30.8 | 31.1 | 37.1 | 14.2 | 49.98 | 23592 | 0.986 | 1.1 | 1 | 0.9 | 14 | 11.9 | 10 |
| 2024 Corr Corr <th< td=""><td></td><td>241.2</td><td>241.9</td><td>240.7</td><td>28.9</td><td>30.9</td><td>36.4</td><td>14</td><td>49.99</td><td>22921</td><td>0.986</td><td>1.1</td><td>1.1</td><td>0.9</td><td>14.6</td><td>12.2</td><td>10.2</td></th<> | | 241.2 | 241.9 | 240.7 | 28.9 | 30.9 | 36.4 | 14 | 49.99 | 22921 | 0.986 | 1.1 | 1.1 | 0.9 | 14.6 | 12.2 | 10.2 |
| 2024 Corr Corr <th< td=""><td>2024</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<> | 2024 | | | | | | | | | | | | | | | | |
| 05-02- 2024 240.8 241.5 240.3 28.7 31.3 37.1 15.1 49.95 23023 0.982 1.1 1.1 0.9 14.9 12.5 10.3 2024 241 241.6 240.4 29 31.3 38.3 16.4 49.98 2321 0.98 1 1 0.8 15.1 12 10.1 2024 241.1 241.8 240.5 29.2 32 37.7 15.4 50 23641 0.982 1.1 1.1 0.9 15.1 12.6 10.2 2024 241.1 241.2 240.7 29.1 31.2 35.6 13.9 50 22762 0.984 1.1 1.1 0.9 15.1 13.2 10.6 20502 241.1 241.2 240.8 29.7 32.8 13.9 29.7 21.984 0.983 1.1 1.2 1 1.4 1.4 1.4 1.4 1.1 1.1 0.9 15.5 | | 240.8 | 241.6 | 240.4 | 29 | 31 | 37.3 | 15 | 49.97 | 23116 | 0.983 | 1 | 1 | 0.8 | 14.6 | 12.4 | 10.1 |
| 05:02- 2024 241 241.6 240.4 29 31.3 38.3 16.4 49:98 2321 0.98 1 1 0.8 15.1 12 10.1 05:02- 2024 241.1 241.8 240.5 29.2 32 37.7 15.4 50 2361 0.982 1.1 1.1 0.9 15.1 12.6 10.2 05:02- 2024 241.1 242.2 240.6 242.2 31.3 35.5 13.6 49.98 2000 0.985 1.1 1.1 0.9 15.1 13.2 10.6 05:02- 2024 241.2 242.2 240.8 29.5 32 35.6 13.5 49.97 2314 0.985 1.1 1.2 1 15.4 13.7 11.1 05:02- 2024 241.3 242.2 241 30.2 30.3 35 14.7 49.97 2264 0.982 1.1 1.2 0.9 15.6 14.8 11.6 05:02- 2024 240.3 </td <td>-</td> <td>240.8</td> <td>241.5</td> <td>240.3</td> <td>28.7</td> <td>31.3</td> <td>37.1</td> <td>15.1</td> <td>49.95</td> <td>23023</td> <td>0.982</td> <td>1.1</td> <td>1.1</td> <td>0.9</td> <td>14.9</td> <td>12.5</td> <td>10.3</td> | - | 240.8 | 241.5 | 240.3 | 28.7 | 31.3 | 37.1 | 15.1 | 49.95 | 23023 | 0.982 | 1.1 | 1.1 | 0.9 | 14.9 | 12.5 | 10.3 |
| 2024 0 | | 241 | 241.6 | 240.4 | 20 | 21.2 | 20.2 | 16.4 | 40.09 | 02201 | 0.09 | 1 | 1 | 0.8 | 15 1 | 12 | 10.1 |
| 2024 C <thc< th=""> <thc< th=""> <thc< th=""> <thc< th=""></thc<></thc<></thc<></thc<> | | 241 | 241.0 | 240.4 | 29 | 31.5 | 38.3 | 10.4 | 49.98 | 23321 | 0.98 | 1 | 1 | 0.8 | 15.1 | 12 | 10.1 |
| 05.02. 241.1 242 240.7 29.1 31.2 36.5 14.9 50 22987 0.983 1.1 1.1 0.9 15.1 12.9 10.4 05-02. 240.6 241.5 240.2 29.1 31.2 35.6 13.9 50 22762 0.984 1.1 1.1 0.9 15.1 13.2 10.6 05-02. 241.1 241.8 240.6 29.2 31.9 35.5 13.6 49.98 23000 0.985 1.1 1.2 1 15.4 13.7 11.1 05-02. 241.3 242.2 241 29.2 31.2 34.8 13.7 49.97 2264 0.983 1.1 1.2 1.5 14.4 11.2 05-02. 241.4 242.2 241 30.2 35.5 16.4 49.97 22842 0.982 1.1 1.2 0.9 15.4 14.5 11.5 05-02. 241.3 242.2 241 31.2 29.5 35.5 16.4 49.95 1968 0.92 1.1 1.2 <td></td> <td>241.1</td> <td>241.8</td> <td>240.5</td> <td>29.2</td> <td>32</td> <td>37.7</td> <td>15.4</td> <td>50</td> <td>23461</td> <td>0.982</td> <td>1.1</td> <td>1.1</td> <td>0.9</td> <td>15</td> <td>12.6</td> <td>10.2</td> | | 241.1 | 241.8 | 240.5 | 29.2 | 32 | 37.7 | 15.4 | 50 | 23461 | 0.982 | 1.1 | 1.1 | 0.9 | 15 | 12.6 | 10.2 |
| 2024 - - - - | - | 241.1 | 242 | 240.7 | 29.1 | 31.2 | 36.5 | 14 9 | 50 | 22987 | 0.983 | 11 | 11 | 0.9 | 15.1 | 12.9 | 10.4 |
| 2024 - - - - | 2024 | | | | | | | | | | | | | | | | |
| 05-02- 2024 241.1 241.8 240.6 29.2 31.9 35.5 13.6 49.98 23000 0.985 1.1 1.1 0.9 14.9 13.4 10.8 05-02- 2024 241.2 242 240.8 29.5 32 35.6 13.5 49.97 23114 0.985 1.1 1.2 1 15.4 13.7 11.1 05-02- 2024 241.3 242.2 241 30.2 30.3 35 14.7 49.98 22718 0.983 1.1 1.2 0.9 15.4 14.5 11.5 05-02- 2024 241.3 242.2 241 31.2 29.5 35.4 15.9 49.97 22842 0.982 1.2 1.2 0.9 15.6 14.8 11.6 05-02- 2024 241.1 242.0 240.6 32.2 29.5 35.5 16.4 49.95 1368 0.92 1.1 1.2 0.9 15.8 15 11.6 05-02- 2024 241.1 242 240.8 28.7 25.5 30.4 16.3 49.95 < | | 240.6 | 241.5 | 240.2 | 29.1 | 31.2 | 35.6 | 13.9 | 50 | 22762 | 0.984 | 1.1 | 1.1 | 0.9 | 15.1 | 13.2 | 10.6 |
| 05:02- 2024 241.2 242 240.8 29.5 32 35.6 13.5 49.97 23114 0.985 1.1 1.2 1 15.4 13.7 11.1 05:02- 2024 241.3 242.2 241 29.2 31.2 34.8 13.7 49.97 22643 0.983 1.1 1.2 0.9 15.5 14 11.2 05:02- 2024 241.4 242.2 241 30.2 30.3 35 14.7 49.98 22718 0.982 1.1 1.2 0.9 15.6 14.8 11.5 05:02- 2024 241.3 242.2 241 31.2 29.5 35.5 16.4 49.95 23068 0.982 1.1 1.2 0.9 15.6 14.8 11.6 05:02- 2024 241.1 242.2 240.6 32.2 29.5 35.5 16.4 49.95 19615 0.982 1.1 1.2 0.9 17.6 19 13.6 05:02- 2024 241.1 242.2 240.6 29.3 24.7 29.8 18.3 49.95 < | | 241.1 | 241.8 | 240.6 | 29.2 | 31.9 | 35.5 | 13.6 | 49.98 | 23000 | 0.985 | 1.1 | 1.1 | 0.9 | 14.9 | 13.4 | 10.8 |
| 2024 - - - - | | 241.2 | 0.40 | 240.0 | 20.5 | 22 | 25.6 | 10.5 | 40.07 | 22114 | 0.007 | 1.1 | 1.0 | 1 | 15.4 | 10.7 | 11.1 |
| 05-02- 2024 241.3 242.2 241 29.2 31.2 34.8 13.7 49.97 22643 0.983 1.1 1.2 0.9 15.5 14 11.2 05-02- 2024 241.4 242.2 241 30.2 30.3 35 14.7 49.98 22718 0.982 1.1 1.2 0.9 15.4 14.5 11.5 05-02- 2024 241.3 242.2 241 31.2 29.5 35.4 15.9 49.97 22842 0.982 1.2 1.2 0.9 15.6 14.8 11.6 05-02- 2024 240.9 241.9 240.6 32.2 29.5 35.5 16.4 49.95 23068 0.982 1.1 1.2 0.9 15.8 15 11.6 05-02- 2024 241.1 242 240.6 32.7 25.5 30.4 16.3 49.95 19253 0.956 1.2 1.2 0.9 17.8 19.9 13.6 05-02- 2024 241.4 242.2 240.6 29.3 24.7 29.8 18.3 49.95 | | 241.2 | 242 | 240.8 | 29.5 | 32 | 35.6 | 13.5 | 49.97 | 23114 | 0.985 | 1.1 | 1.2 | 1 | 15.4 | 13.7 | 11.1 |
| 05-02- 2024 241.4 242.2 241 30.2 30.3 35 14.7 49.98 22718 0.982 1.1 1.2 0.9 15.4 14.5 11.5 05-02- 2024 241.3 242.2 241 31.2 29.5 35.4 15.9 49.97 22842 0.982 1.2 1.2 0.9 15.6 14.8 11.6 05-02- 2024 240.9 241.9 240.6 32.2 29.5 35.5 16.4 49.95 23068 0.982 1.1 1.2 0.9 15.6 14.8 11.6 05-02- 2024 241.1 242 240.8 28.7 25.5 30.4 16.3 49.96 19615 0.958 1.1 1.2 0.9 17.6 19 13.6 05-02- 2024 241.4 242.4 241.1 28.9 24.9 29.3 16.9 49.95 19360 0.956 1.1 1.2 0.9 17.8 19.9 13.7 05-02- 2024 240.5 241.4 240.2 29.9 24.8 28.1 17.1 49.89 | 05-02- | 241.3 | 242.2 | 241 | 29.2 | 31.2 | 34.8 | 13.7 | 49.97 | 22643 | 0.983 | 1.1 | 1.2 | 0.9 | 15.5 | 14 | 11.2 |
| 2024 6 <th6< th=""> 6 6 6</th6<> | - | 241.4 | 242.2 | 241 | 30.2 | 30.3 | 35 | 14.7 | 49.98 | 22718 | 0.982 | 11 | 12 | 0.9 | 15.4 | 14.5 | 11.5 |
| 2024 1 | | 2-11 | 242.2 | 241 | 50.2 | 50.5 | 55 | 14.7 | 47.90 | 22710 | 0.902 | 1.1 | 1.2 | 0.9 | 15.4 | 14.5 | 11.5 |
| 05-02- 2024 240.9 241.9 240.6 32.2 29.5 35.5 16.4 49.95 23068 0.982 1.1 1.2 0.9 15.8 15 11.6 05-02- 2024 241.1 242 240.8 28.7 25.5 30.4 16.3 49.96 19615 0.958 1.1 1.2 0.9 17.6 19 13.6 05-02- 2024 241.4 242.4 241.1 28.9 24.9 29.3 16.9 49.95 19253 0.956 1.2 1.2 0.9 17.8 19.9 13.7 05-02- 2024 241 242 240.6 29.3 24.7 29.8 18.3 49.95 19360 0.956 1.1 1.2 0.9 17.3 20.2 13.6 05-02- 2024 240.5 241.4 240.2 29.9 24.2 28.1 17.1 49.89 18925 0.953 1.1 1.2 0.9 17. 20.2 13.5 05-02- 2024 240.6 241.2 239.9 30.6 24.2 28.4 17.5 49.87 | | 241.3 | 242.2 | 241 | 31.2 | 29.5 | 35.4 | 15.9 | 49.97 | 22842 | 0.982 | 1.2 | 1.2 | 0.9 | 15.6 | 14.8 | 11.6 |
| 05-02- 2024 241.1 242 240.8 28.7 25.5 30.4 16.3 49.96 19615 0.958 1.1 1.2 0.9 17.6 19 13.6 05-02- 2024 241.4 242.4 241.1 28.9 24.9 29.3 16.9 49.95 19253 0.956 1.2 1.2 0.9 17.8 19.9 13.7 05-02- 2024 241 242 240.6 29.3 24.7 29.8 18.3 49.95 19360 0.956 1.1 1.2 0.9 17.3 20.2 13.6 05-02- 2024 240.5 241.4 240.2 29.9 24.8 29.3 17.9 49.93 19360 0.956 1.1 1.2 0.9 17. 20.2 13.5 05-02- 2024 240.6 241.5 240.3 29.9 24.2 28.1 17.1 49.89 18925 0.953 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 240.3 241.7 240.6 30.9 24.4 28.7 17.7 49.9 | - | 240.9 | 241.9 | 240.6 | 32.2 | 29.5 | 35.5 | 16.4 | 49.95 | 23068 | 0.982 | 1.1 | 1.2 | 0.9 | 15.8 | 15 | 11.6 |
| 2024 1 | - | 0.11.1 | 2.12 | 240.0 | 20.7 | 25.5 | 20.4 | 160 | 10.04 | 10 (15 | 0.050 | | 1.2 | | 15.6 | 10 | 10 (|
| 05-02- 2024 241.4 242.4 241.1 28.9 24.9 29.3 16.9 49.95 19253 0.956 1.2 1.2 0.9 17.8 19.9 13.7 05-02- 2024 241 242 240.6 29.3 24.7 29.8 18.3 49.95 19360 0.956 1.1 1.2 0.9 17.8 19.9 13.7 05-02- 2024 240.5 241.4 240.2 29.9 24.8 29.3 17.9 49.93 19360 0.956 1.1 1.2 0.9 17. 20.2 13.5 05-02- 2024 240.6 241.5 240.3 29.9 24.2 28.1 17.1 49.89 18925 0.955 1.1 1.2 0.9 16.8 20.6 13.8 05-02- 2024 240.6 241.2 239.9 30.6 24.2 28.4 17.5 49.87 19155 0.955 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 2024 241 241.7 240.6 30.9 24.4 28.7 17.7 49.93 </td <td></td> <td>241.1</td> <td>242</td> <td>240.8</td> <td>28.7</td> <td>25.5</td> <td>30.4</td> <td>16.3</td> <td>49.96</td> <td>19615</td> <td>0.958</td> <td>1.1</td> <td>1.2</td> <td>0.9</td> <td>17.6</td> <td>19</td> <td>13.6</td> | | 241.1 | 242 | 240.8 | 28.7 | 25.5 | 30.4 | 16.3 | 49.96 | 19615 | 0.958 | 1.1 | 1.2 | 0.9 | 17.6 | 19 | 13.6 |
| 05-02- 2024 241 242 240.6 29.3 24.7 29.8 18.3 49.95 19360 0.956 1.1 1.2 0.9 17.3 20.2 13.6 05-02- 2024 240.5 241.4 240.2 29.9 24.8 29.3 17.9 49.93 19360 0.956 1.1 1.2 0.9 17.3 20.2 13.5 05-02- 2024 240.6 241.5 240.3 29.9 24.2 28.1 17.1 49.89 18925 0.953 1.1 1.2 0.9 16.8 20.6 13.8 05-02- 2024 240.3 241.2 239.9 30.6 24.2 28.4 17.5 49.87 19155 0.955 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 2024 241 241.7 240.6 30.9 24.4 28.7 17.7 49.9 19388 0.955 1.1 1.2 0.9 16.7 19.9 14.5 05-02- 2024 240.4 241.2 239.9 30.5 24.7 28.5 17.2 49.93 </td <td>05-02-</td> <td>241.4</td> <td>242.4</td> <td>241.1</td> <td>28.9</td> <td>24.9</td> <td>29.3</td> <td>16.9</td> <td>49.95</td> <td>19253</td> <td>0.956</td> <td>1.2</td> <td>1.2</td> <td>0.9</td> <td>17.8</td> <td>19.9</td> <td>13.7</td> | 05-02- | 241.4 | 242.4 | 241.1 | 28.9 | 24.9 | 29.3 | 16.9 | 49.95 | 19253 | 0.956 | 1.2 | 1.2 | 0.9 | 17.8 | 19.9 | 13.7 |
| 2024 1 <t< td=""><td></td><td>241</td><td>242</td><td>240.6</td><td>29.3</td><td>24.7</td><td>29.8</td><td>18.3</td><td>49.95</td><td>19360</td><td>0.956</td><td>11</td><td>12</td><td>0.9</td><td>17.3</td><td>20.2</td><td>13.6</td></t<> | | 241 | 242 | 240.6 | 29.3 | 24.7 | 29.8 | 18.3 | 49.95 | 19360 | 0.956 | 11 | 12 | 0.9 | 17.3 | 20.2 | 13.6 |
| 2024 <th< td=""><td></td><td>271</td><td>242</td><td></td><td>27.5</td><td></td><td>27.0</td><td>10.5</td><td>ч<i>).)</i> 5</td><td>17500</td><td>0.950</td><td>1.1</td><td>1.2</td><td></td><td></td><td></td><td>15.0</td></th<> | | 271 | 242 | | 27.5 | | 27.0 | 10.5 | ч <i>).)</i> 5 | 17500 | 0.950 | 1.1 | 1.2 | | | | 15.0 |
| 05-02- 2024 240.6 241.5 240.3 29.9 24.2 28.1 17.1 49.89 18925 0.953 1.1 1.2 0.9 16.8 20.6 13.8 05-02- 2024 240.3 241.2 239.9 30.6 24.2 28.4 17.5 49.87 19155 0.955 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 2024 241 241.7 240.6 30.9 24.4 28.7 17.7 49.9 19388 0.955 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 2024 241.0 241.2 239.9 30.2 24.7 28.5 17.2 49.93 19110 0.952 1.2 1.2 1 17.1 20.5 14.6 05-02- 2024 240.4 241.2 239.9 30.5 24.7 28.9 17.4 49.92 19249 0.953 1.3 1.3 1.1 16.8 20.3 14.1 05-02- 2024 240.7 240.5 239.8 30.5 25.7 29.1 17.5 49.94 | | 240.5 | 241.4 | 240.2 | 29.9 | 24.8 | 29.3 | 17.9 | 49.93 | 19360 | 0.956 | 1.1 | 1.2 | 0.9 | 17 | 20.2 | 13.5 |
| 05-02- 2024 240.3 241.2 239.9 30.6 24.2 28.4 17.5 49.87 19155 0.955 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 2024 241 241.7 240.6 30.9 24.4 28.7 17.7 49.9 19388 0.955 1.1 1.2 0.9 16.4 20.4 13.4 05-02- 2024 240.4 241.2 239.9 30.2 24.7 28.5 17.2 49.93 19110 0.952 1.2 1.2 1 17.1 20.5 14.6 05-02- 2024 240.4 241.2 239.9 30.2 24.7 28.5 17.2 49.93 19110 0.952 1.2 1.2 1 17.1 20.5 14.6 05-02- 2024 239.5 240.5 239 30.5 24.7 28.9 17.4 49.92 19249 0.953 1.3 1.3 1.1 16.8 20.3 14.1 05-02- 2024 240.7 241.5 240.2 30.5 25 29.1 17.5 49.94 | | 240.6 | 241.5 | 240.3 | 29.9 | 24.2 | 28.1 | 17.1 | 49.89 | 18925 | 0.953 | 1.1 | 1.2 | 0.9 | 16.8 | 20.6 | 13.8 |
| 2024 | | 240.2 | 241.2 | 220.0 | 20.6 | 24.2 | 20.4 | 17.5 | 40.07 | 10155 | 0.055 | | 1.2 | | 164 | 20.4 | 10.4 |
| 05-02- 2024 241 241.7 240.6 30.9 24.4 28.7 17.7 49.9 19388 0.955 1.1 1.2 0.9 16.7 19.9 14.5 05-02- 2024 240.4 241.2 239.9 30.2 24.7 28.5 17.2 49.93 19110 0.952 1.2 1.2 1 17.1 20.5 14.6 05-02- 2024 239.5 240.5 239 30.5 24.7 28.5 17.2 49.93 19110 0.952 1.2 1.2 1 17.1 20.5 14.6 05-02- 2024 239.5 240.5 239 30.5 24.7 28.9 17.4 49.92 19249 0.953 1.3 1.3 1.1 16.8 20.3 14.1 05-02- 2024 240.7 241.5 240.2 30.5 25 29.1 17.5 49.94 19451 0.952 1.3 1.3 1.1 17 20.5 14 05-02- 2024 240.3 241.3 239.8 30.4 25.3 28.9 17.1 49.93 | | 240.3 | 241.2 | 239.9 | 30.6 | 24.2 | 28.4 | 17.5 | 49.87 | 19155 | 0.955 | 1.1 | 1.2 | 0.9 | 16.4 | 20.4 | 13.4 |
| 05-02- 2024 240.4 241.2 239.9 30.2 24.7 28.5 17.2 49.93 19110 0.952 1.2 1.2 1 17.1 20.5 14.6 05-02- 2024 239.5 240.5 239 30.5 24.7 28.9 17.4 49.92 19249 0.953 1.3 1.3 1.1 16.8 20.3 14.1 05-02- 2024 240.7 241.5 240.2 30.5 25 29.1 17.5 49.94 19451 0.952 1.3 1.3 1.1 16.8 20.3 14.1 05-02- 2024 240.7 241.5 240.2 30.5 25 29.1 17.5 49.94 19451 0.952 1.3 1.3 1.1 16.8 20.3 14.1 05-02- 2024 240.3 241.3 239.8 30.4 25.3 28.9 17.1 49.93 19427 0.953 1.3 1.4 1.1 16.9 20.4 14.1 05-02- 2024 240.3 241.3 239.8 30.4 25.3 28.9 17.1 49.93 <td>05-02-</td> <td>241</td> <td>241.7</td> <td>240.6</td> <td>30.9</td> <td>24.4</td> <td>28.7</td> <td>17.7</td> <td>49.9</td> <td>19388</td> <td>0.955</td> <td>1.1</td> <td>1.2</td> <td>0.9</td> <td>16.7</td> <td>19.9</td> <td>14.5</td> | 05-02- | 241 | 241.7 | 240.6 | 30.9 | 24.4 | 28.7 | 17.7 | 49.9 | 19388 | 0.955 | 1.1 | 1.2 | 0.9 | 16.7 | 19.9 | 14.5 |
| 2024 | | 240.4 | 241.2 | 230.0 | 30.2 | 247 | 28.5 | 17.2 | 49.03 | 19110 | 0.052 | 12 | 12 | 1 | 17.1 | 20.5 | 14.6 |
| 2024 | 2024 | 240.4 | 241.2 | | 50.2 | 24.7 | 20.5 | 17.2 | +7.75 | 17110 | | 1.2 | 1.2 | 1 | 17.1 | 20.5 | 14.0 |
| 05-02- 2024 240.7 241.5 240.2 30.5 25 29.1 17.5 49.94 19451 0.952 1.3 1.3 1.1 17 20.5 14 05-02- 2024 240.3 241.3 239.8 30.4 25.3 28.9 17.1 49.93 19427 0.953 1.3 1.4 1.1 16.9 20.4 14.1 | | 239.5 | 240.5 | 239 | 30.5 | 24.7 | 28.9 | 17.4 | 49.92 | 19249 | 0.953 | 1.3 | 1.3 | 1.1 | 16.8 | 20.3 | 14.1 |
| 2024 | | 240.7 | 241.5 | 240.2 | 30.5 | 25 | 29.1 | 17.5 | 49.94 | 19451 | 0.952 | 1.3 | 1.3 | 1.1 | 17 | 20.5 | 14 |
| 2024 | 2024 | | | | | | | | | | | | | | | | |
| | | 240.3 | 241.3 | 239.8 | 30.4 | 25.3 | 28.9 | 17.1 | 49.93 | 19427 | 0.953 | 1.3 | 1.4 | 1.1 | 16.9 | 20.4 | 14.1 |
| | | 240 | 240.9 | 239.5 | 30.5 | 25.1 | 28.6 | 17.2 | 49.93 | 19284 | 0.952 | 1.2 | 1.3 | 1.1 | 16.6 | 20.8 | 14 |

| 2024 | | | | | | | | | | | | | | | | 1 |
|----------------|--------|-------|--------|------|------|------|------|-------|--------|-------|-----|-----|-----|------|------|------|
| 05-02- | 240.9 | 241.8 | 240.5 | 35.2 | 25.2 | 28.5 | 19.1 | 49.93 | 20724 | 0.965 | 1.1 | 1.2 | 0.9 | 15.6 | 20.4 | 13.9 |
| 2024 05-02- | 241.2 | 242.3 | 241 | 36.8 | 25.7 | 28.4 | 19 | 49.93 | 21401 | 0.972 | 1.1 | 1.2 | 1 | 15.6 | 20.3 | 13.9 |
| 2024 | 241.2 | 242.5 | 241 | 30.8 | 23.7 | 20.4 | 19 | 49.95 | 21401 | 0.972 | 1.1 | 1.2 | 1 | 13.0 | 20.5 | 15.9 |
| 05-02- 2024 | 241.4 | 242.3 | 241 | 37.2 | 25.4 | 28.7 | 19.7 | 49.94 | 21509 | 0.973 | 1 | 1.1 | 0.9 | 15.4 | 20 | 13.6 |
| 05-02- | 240.8 | 241.6 | 240.2 | 37.2 | 25.5 | 30.2 | 21.1 | 49.93 | 21818 | 0.973 | 1 | 1.1 | 0.9 | 15.2 | 19.6 | 13.2 |
| 2024 05-02- | 240.9 | 241.6 | 240.2 | 37 | 24.0 | 20 | 21.2 | 40.01 | 21606 | 0.974 | 1 | 1.1 | 0.0 | 15.1 | 10.7 | 12.4 |
| 2024 | 240.8 | 241.6 | 240.2 | 57 | 24.9 | 30 | 21.3 | 49.91 | 21000 | 0.974 | 1 | 1.1 | 0.9 | 15.1 | 18.7 | 13.4 |
| 05-02- 2024 | 241.1 | 242.1 | 240.8 | 37 | 25.3 | 29 | 19.4 | 49.9 | 21537 | 0.976 | 1 | 1.1 | 0.9 | 15.5 | 18 | 13.8 |
| 05-02- | 241.4 | 242.3 | 241.1 | 37.5 | 25 | 28.8 | 19.9 | 49.89 | 21547 | 0.975 | 1 | 1.1 | 0.8 | 15.3 | 18.1 | 13.7 |
| 2024 05-02- | 240.9 | 241.9 | 240.6 | 38.2 | 25.3 | 29.1 | 20.6 | 49.87 | 21804 | 0.974 | 1 | 1.1 | 0.9 | 15.1 | 18.2 | 13.8 |
| 2024 | 240.9 | 241.9 | 240.0 | 30.2 | 23.3 | 29.1 | 20.0 | 49.07 | 21004 | 0.974 | 1 | 1.1 | 0.9 | 15.1 | 10.2 | 15.8 |
| 05-02- 2024 | 241.4 | 242.4 | 241.2 | 43.3 | 25.3 | 29.2 | 24.2 | 49.93 | 23166 | 0.979 | 1 | 1.1 | 0.8 | 13.4 | 17.9 | 13.9 |
| 05-02- | 241.5 | 242.5 | 241.3 | 43.7 | 25.4 | 29 | 24 | 49.95 | 23312 | 0.98 | 1 | 1.1 | 0.9 | 13.3 | 17.5 | 13.8 |
| 2024 05-02- | 241.7 | 242.8 | 241.5 | 38.8 | 25.9 | 29.1 | 19.3 | 49.99 | 22278 | 0.979 | 0.9 | 1.1 | 0.8 | 14.7 | 16.7 | 13.5 |
| 2024 | 241.7 | 242.0 | 241.3 | 50.0 | 23.9 | 29.1 | 19.5 | 49.99 | 22278 | 0.979 | 0.9 | 1.1 | 0.8 | 14.7 | 10.7 | 15.5 |
| 05-02- 2024 | 241.4 | 242.5 | 241.1 | 38.5 | 26.3 | 29.5 | 18.9 | 50.02 | 22310 | 0.978 | 0.9 | 1 | 0.8 | 14.5 | 17 | 13.6 |
| 05-02- | 242 | 243.1 | 241.8 | 42.6 | 34.9 | 30.6 | 16.4 | 50.04 | 25811 | 0.984 | 0.9 | 1 | 0.7 | 12.9 | 12.4 | 13.1 |
| 2024 05-02- | 242.7 | 243.8 | 242.4 | 38.7 | 32 | 42.2 | 18.6 | 50.05 | 27062 | 0.985 | 0.9 | 1 | 0.7 | 13.9 | 13.8 | 9.3 |
| 2024 | | | | | | | | | | | | | | | | |
| 05-02- 2024 | 243 | 244.1 | 242.7 | 37.2 | 26.6 | 42.4 | 23 | 50.06 | 25381 | 0.981 | 0.8 | 0.9 | 0.7 | 14.3 | 16.9 | 9.1 |
| 05-02- | 242.7 | 243.8 | 242.2 | 32.7 | 26.1 | 41.9 | 24.8 | 50.04 | 23820 | 0.972 | 0.9 | 1 | 0.7 | 15.8 | 17.5 | 9.3 |
| 2024 05-02- | 243 | 244.1 | 242.7 | 32.8 | 26 | 35.4 | 21.1 | 50.04 | 22262 | 0.969 | 0.8 | 0.9 | 0.7 | 15.7 | 17.3 | 11.1 |
| 2024 | 0.40.1 | 044.1 | 0.40.7 | 21.0 | 25.0 | 20 | 167 | 50.02 | 2020.6 | 0.064 | 0.0 | 1 | 0.7 | 161 | 17.6 | 12.4 |
| 05-02- 2024 | 243.1 | 244.1 | 242.7 | 31.9 | 25.9 | 29 | 16.7 | 50.03 | 20396 | 0.964 | 0.9 | 1 | 0.7 | 16.1 | 17.6 | 13.4 |
| 05-02- | 242.9 | 243.9 | 242.6 | 31.9 | 25.9 | 28.9 | 16.5 | 50.01 | 20356 | 0.963 | 0.9 | 0.9 | 0.7 | 16.1 | 17.9 | 13.7 |
| 2024 05-02- | 242.9 | 243.8 | 242.6 | 31.5 | 25.8 | 28.8 | 16.3 | 50.01 | 20188 | 0.963 | 0.9 | 1 | 0.8 | 16.4 | 18.1 | 13.7 |
| 2024 | | | | | | | | 49.98 | | | 0.0 | | | | | |
| 05-02- 2024 | 242.6 | 243.4 | 242.2 | 33 | 25.9 | 28.7 | 17.1 | 49.98 | 20543 | 0.964 | 0.9 | 0.9 | 0.7 | 15.9 | 18.3 | 13.8 |
| 05-02- 2024 | 242.5 | 243.6 | 242.3 | 38.4 | 26.1 | 28.7 | 20 | 49.94 | 21985 | 0.97 | 0.9 | 0.9 | 0.7 | 13.9 | 18.4 | 13.8 |
| 05-02- | 242.1 | 243 | 241.7 | 38.4 | 26 | 28.3 | 20.3 | 49.93 | 21787 | 0.968 | 1 | 1 | 0.8 | 14.3 | 19 | 14.2 |
| 2024 | 241.6 | 242.5 | 241.2 | 38.6 | 25.4 | 28.1 | 20.3 | 49.93 | 21644 | 0.969 | 1 | 1 | 0.8 | 14.4 | 18 | 14.2 |
| 05-02- 2024 | 241.6 | 242.5 | 241.2 | 38.0 | 25.4 | 26.1 | 20.5 | | 21044 | 0.909 | 1 | 1 | 0.8 | 14.4 | 10 | 14.2 |
| 05-02- 2024 | 242 | 243 | 241.7 | 32 | 24.9 | 27.8 | 16.4 | 49.99 | 19770 | 0.962 | 0.9 | 1 | 0.7 | 16.7 | 18 | 14 |
| 05-02- | 242.2 | 243.2 | 242 | 31.9 | 24.7 | 28 | 16.8 | 50.01 | 19762 | 0.961 | 0.9 | 1 | 0.7 | 16.7 | 17.7 | 13.7 |
| 2024 05-02- | 242.3 | 243.2 | 241.9 | 32 | 24.7 | 28.2 | 17.1 | 49.98 | 19825 | 0.961 | 0.9 | 0.9 | 0.7 | 16.5 | 18 | 13.6 |
| 2024 | | | | | | | | | | | | | | | | |
| 05-02- 2024 | 242.4 | 243.4 | 242.1 | 32.1 | 24.5 | 29.9 | 18.8 | 49.99 | 20229 | 0.961 | 0.8 | 0.9 | 0.7 | 16.2 | 17.6 | 12.6 |
| 05-02- | 241.7 | 242.7 | 241.4 | 37.5 | 30.2 | 37.3 | 19.7 | 49.99 | 25015 | 0.982 | 0.9 | 1 | 0.7 | 14.2 | 12.8 | 10.1 |
| 2024 05-02- | 241.7 | 242.8 | 241.2 | 37.7 | 29.8 | 36.1 | 18.6 | 49.99 | 24733 | 0.985 | 0.9 | 1 | 0.7 | 14.2 | 13.6 | 10.3 |
| 55 62 | 2.11./ | 2.2.0 | - 11.2 | 57.1 | 27.0 | 55.1 | 10.0 | | 2.755 | 0.705 | 0.7 | 1 | 0.7 | 11.2 | 10.0 | 10.5 |


2023-24

| 2024 | | | | | | | | | | | | | | | | |
|----------------|-------|-------|-------|------|------|------|------|-------|-------|-------|-----|-----|-----|------|------|------|
| 05-02- 2024 | 241.3 | 242.4 | 240.8 | 37.7 | 29.8 | 35.6 | 18.3 | 49.99 | 24566 | 0.985 | 0.9 | 0.9 | 0.7 | 14.5 | 13.7 | 10.6 |
| 05-02- 2024 | 240.7 | 241.6 | 240 | 38.7 | 29.6 | 36.4 | 19.5 | 49.96 | 24869 | 0.985 | 1 | 1 | 0.8 | 14.5 | 13.9 | 10.2 |


5.2 Variation in Electrical Parameters

Now we present the variation in various Electrical parameters as under.


5.2.1 Voltage




5.2.2 Current




5.2.3 Total Active power (kW)




5.2.4 Power factor



5.2.5 Voltage THD%



5.2.6 Current THD%



CHAPTER-VI SCOPE OF RENEWABLE ENERGY AND EFFICIENT FACILITY AT COLLEGE CAMPUS

6.1 Installation of 50 kWp Solar PV roof Top on Bharati Vidyapeeth's College of Engineering building:

During the Audit, it was revealed that the College has ample space on the Terrace but top two floors under construction. It is proposed once construction completes Solar Photovoltaic roof top with net meter of capacity **50 kWp can be installed.** The system will cater the Day load Demand of the College.

We furnish herewith the saving potential as under

| No | Particulars | Value | Unit |
|----|---|----------|-------------|
| 1 | Installed Capacity of Solar PV Pack | 50 | kWp |
| 2 | Daily working period | 6 | Hrs./Day |
| 3 | Daily units generated | 300 | kWh/Day |
| 4 | Annual working days | 280 | Day/annum |
| 5 | Annual saving in Grid Electrical Energy | 84000 | kWh/annum |
| 6 | Annual CO ₂ saving potential | 67.2 | MT/Annum |
| 7 | Present Energy Charges | 10 | Rs/kWh |
| 8 | Annual monetary Gain | 840000 | Rs/Annum |
| 9 | Investment required | 22,50000 | Rs lump sum |
| 10 | Payback period | 2.67 | Years |

6.2 Solar Water heater

Today we are facing the shortage problem between supply and demand of electric energy especially during peak summer and winter seasons. The situation further worsens during early hours of peak winter season when enormous heating load is switched 'ON'. This has been a consistent problem. If the heating load is switched over to non-conventional source of energy, from conventional energy sources, the gap can be bridged considerably. 'Solar Energy' is an unlimited source of non-conventional energy. Solar energy can provide cost-effective solutions to fight climate change and reduce our dependency on expensive and polluting fuels. A solar water heater is an efficient and reliable technology that converts sunlight into heat to produce your hot water. At present Bharati Vidyapeeth's College of Engineering, Lavale campus uses electric gysers in 24 nos. having capacity of 15 litrs and 3 kW coil for hot water production in boys hostel.



Photo-1: Electric heaters in the boys hotel at BV CoE, Lavale, Pune

Solar water heating system of total capacity of 1000 LPD can be used to provide hot water for bathing purpose for students, which will decrease the electrical energy consumption.

6.3 Solar powered light for hoarding

Lighting solar systems are the fixed installations designed for domestic as well as small scale commercial application. The component of the solar lighting system includes solar PV module (solar cells), charge controller, solar battery and lighting system (lamps & fans). Modules are installed in the open on roof/terrace - exposed to sunlight and the charge controller and battery are kept inside a protected place in the house.



Figure-1: Solar powered light for Hoarding

This system comes with multiple benefits such as:

- **Economical:** Since the sun provides energy free of charge, 30% power savings on the electricity bill can be availed with longer back up lighting system at zero running cost.
- **Non-Polluting:** Powered by the sun's renewable energy, the system is energy neutral and an absolutely clean source of illumination. 1kWp solar installation reduces 1/2 ton of CO₂ (carbon dioxide) per annum.
- **No Maintenance:** The system has few moveable parts reducing the risk of breakage. Once installed, it lasts for long time and requires little attention.

This system can be used to power the huge hoardings in the college campus.

Solar powered hoarding lighting system proposed will provide a better, faster, cheaper (and cleaner) alternative with solar. Since this product competes with diesel or conventional fuels, we needed to ensure we beat the cost of a diesel solution. In order to achieve that with solar, we consider the following system:

1. Highly Efficient Solar Panel

2. Charge Controllers with MPPT Technology – increases solar electricity production by up to 30% compared to conventional charge controllers

3. LED Projection Light – consumes 10-times less electricity compared to conventional bulbs, and has a 50,000 hour warranty.

Features:

Auto on off


2023-24


- 4 Days Battery Back Up
- Robust housing
- Weather proof

With this entire put together, we ended up with systems that provide 6 hours of lighting each night with 4 -lamp system to light up boards up to 15'x30', and a 8-lamp system to light larger boards up to 20'x40'. More importantly, with these options, payback of the system will come around 2.5 years. This system provides a way to reduce the lightings costs, get rid of all the operational hassles of owning a diesel generator, plus brand benefits from being "green" with the use of renewable energy like solar powered light hoarding board.

6.4 Solar charging stations

Solar cell phone chargers use solar panels to charge cell phone batteries. They are an alternative to conventional electrical cell phone chargers and in some cases can be plugged into an electrical outlet. Solar mobile charger is a device which can charge mobile phones using solar radiation. Its major component is a compact solar panel. This solar panel traps solar energy and produces an output voltage. But, since the light radiations falling on the solar panel can vary, the output voltage becomes unstable. For charging a mobile phone, stable voltage is required. So, to make the output voltage stable and regulated, voltage regulator circuit along with the solar panel is used.





Most of the mobile phones have computer connectivity via USB cable. USB port establishes 4 connection terminals. The connection terminals at the two extreme ends are the supply terminals. In a female USB connector (port via which we plug in USB devices to computer), these terminals carry 5V DC. When a mobile phone is connected to the USB port of a computer, it utilizes this 5V supply to recharge battery. This feature is used in a solar mobile charger. It converts and regulates solar energy to 5V DC and the output will be available through the female USB connector, we can easily connect a mobile phone via data cable.

Chapter VII SUGGESTIONS AND RECOMMENDATIONS

Following Energy Conservation Opportunities and actions on the basis of energy audit are suggested to implement in the campus on the basis of funds availability and institute preferences.

a) Energy Audit: Energy Conservation opportunities:

- The contract demand is 460 KVA, but actual maximum demand is very less so the demand charges are heavily paid evry month by the consumer. The contract demand may be lower down with the consideration of expansion of the Institute.
- APFC of 270KVAr is already installed at the main electrical panel with steps of 50, 20, 10 and 5. Still there is a difference between KVAh and kWh. The APFC can be fine-tuned with lower steps.
- Energy efficient tubes and fans can be replaced. Already the phasing out of old tubes has been undertaken during regular maintenance practices.
- Installation of 50 kW solar roof top system as ample space available on the roof of the college building. At present top floor construction is going on, Once it is over, roof area can be used for the installation of solar roof top. As sanctioned load is 771.5 kW, the solar roof top of 50 kW capacity with net meter can be installed in the college campus to meet the requirement of electricity.
- Installation of Solar powered light for hoarding.
- > Installation of 05 Nos. solar mobile phone charging stations in the college campus.
- Water management system must be in place. Overhead tanks can be with float control and Time of the day (TOD) can be implemented for water pumping for filling the overhead water tanks.

Environmental and Green Audit Report

of

Bharati Vidyapeeth's

College of Engineering

Lavale, Pune



Auditing Agency – Prathamesh Energy Solution, A-302, Shiv Unnati Residency, Kalepadal, Hadapsar Pune- 411 028

Prathamesh Energy Solution

A-302, Shiv Unnati residency, Kalepadal, Hadapsar, Pune-411028

Ref: PES/BVCOEL/2023-24/59

Date: 07/02/2024

To,

The Principal Bharati Vidyapeeth's College of Engineering, Lavale, Pune

Sub: Submission of Report on Environmental and Green Audit of College Campus

Respected Sir,

Please find enclosed herewith the report

Thanking you Yours faithfully

For Prathamesh Energy Solution

Authorized Signatory

Prathamesh Energy Solution

A-302, Shiv Unnati Residency, Kalepadal, Hadapsar, Pune 411028

Ref: EC/BVCOEL/2023-24/60

CERTIFICATE

This is to certify that we have conducted Environmental and Green Audit at **Bharati Vidyapeeth's College of Engineering, Lavale, Pune,** in the Academic year 2023-24

. The College has adopted following Energy Efficient practices:

- Usage of Energy Efficient LED Fittings
- Maximum usage of Day Lighting
- Green Campus
- Rain water Harvesting system

We appreciate the support of Management, involvement of faculty members and students in the process of making the Campus Energy Efficient.

For,

Prathamesh Energy Solution,

This is to Certify that Environmental Management System of

PRATHAMESH ENERGY SOLUTION

A-302, SHIV UNNATI RESIDENCY, KALEPADAL, HADAPSAR, PUNE-411028, MAHARASHTRA, INDIA.

has been assessed and found to conform to the requirements of

14001:2015 for the following scope :

CONSULTANCY SERVICES FOR ENERGY AUDIT, GREEN AUDIT AND ENVIRONMENTAL AUDIT IN EDUCATIONAL INSTITUTIONS AND OTHER ORGANIZATIONS & SUBMISSION OF AUDIT CERTIFICATE AND REPORT.

Certificate No Initial Registration Date : 09/06/2023 Date of Expiry 1st Surve. Due

SO

Sevtificate

: 23EELA98 : 08/06/2026 : 09/05/2024

Issuance Date : 09/06/2023

Registration

2nd Surve. Due : 09/05/2025





| Sr. No | Particulars | Page No |
|--------|---|---------|
| I | Acknowledgement | 7 |
| II | Executive Summary | 8 |
| | Abbreviations | 10 |
| | | |
| 1 | Environment and Green Audit: Introduction | 11 |
| 2 | Green Audit for AY-2023-24 | 12 |
| | 1. Plantation in the campus | 12 |
| | 2. Carbon foot-printing | 18 |
| | Usage of renewable energy at college campus | 21 |
| | 4. Illumination in class rooms | 25 |
| | 5. Water Audit and Rain water harvesting | 26 |
| | 6. Waste disposal | 30 |
| 3 | Suggestions and Recommendations | 34 |

INDEX

ACKNOWLEDGEMENT

We at Prathamesh Energy Solution, Pune, express our sincere gratitude to the management and Principal of Bharati Vidyapeeth's College of Engineering, Lavale, Pune for awarding us the assignment of Energy Audit and Green audit/Environmental audit of their College campus located at Lavale, Pune.

We are very much thankful to

- Dr. Vishwajeet Kadam, Secretary Bharati Vidyapeeth, Pune
- Dr. Shivajirao Kadam, Chancellor, Bharati Vidyapeeth Deemed to be University.
- Dr. K D Jadhav, Jt. Secretary (Admin), bharati Vidyapeeth, Pune
- Dr. R N Patil, Principal, Bharati Vidyapeeth's College of Engineering, Lavale, Pune

for giving us opportunity to conduct detailed energy audit of the institute and provide all the required data and information promptly for the smooth conduction of detailed energy and green audit.

We are also thankful to various Heads of Departments, IQAC Coordinator & other Staff members for helping us during the survey and field visit.

We are also thankful to all the technical staff and office staff for helping during the field visit and measurements at the college campus.

EXECUTIVE SUMMARY

After the Field measurements & analysis, we present herewith important observations made and various measures to reduce the Energy Consumption & mitigate the CO₂ emissions

1. Bharati Vidyapeeth's College of Engineering, Lavale, Pune, consumes electrical Energy in majority used for various gadgets & office operations.

2. The various projects already implemented by the College are

- > Installed APFC of 270 kVAR at Main electrical distribution to maintain Power factor.
- Usage of natural day lights and natural air circulation
- Usage of Natural Day light in corridors specifically
- Usage of LED lighting for Admin & outdoor lighting
- > Initiatives for water conservation through STP at the campus

3. Important Parameters: Electrical Energy:

Electricity is used for different purposes and at different sections in the college campus. The details of electricity distribution as mentioned below.

| Sr. No. | Consumer No. | Electrical Meter No. | Location/Purpose | Payee |
|------------|-----------------|-------------------------|---|--|
| 1 | 182829055190 | 076- 05040425 | College building/building operation | M/S. Joint Secretary Bharati Vidyapeeth College of Engineering, Lavale |

The important parameters of electrical consumption as per Consumer no. in the campus are mentioned as below.

| Sr. No | Consumer No. | Parameter | Max | Min | Average |
|-----------|---------------|-------------------------|--------|--------|-----------|
| 1 | 4 40000055400 | Units consumed, kVAh | 26246 | 14403 | 18447.33 |
| | 182829055190 | Electricity Bill amount | 516876 | 347361 | 406580.3 |
| | | Total | | | 425027.63 |

4. Important Parameters: CO₂ Emissions (Average, MT/Annum)

| | Consumer No. | | Value |
|----|--------------|--|--------|
| No | | Particulars | МТ |
| 1 | 182829055190 | CO ₂ - Emissions- Electricity Usage | 177.09 |
| | | Total | 177.09 |

On the basis of average electricity consumption CO_2 emission is 177.09 MT /annum. In addition to this LPG is being consumed for canteen for food preparation. Nearly LPG consumption annually is 12 commercial cylinders i.e. 228 kg/annum. On the basis of average LPG usage CO_2 emission is 0.68MT/annum.

5. Benchmark: In terms of Electrical Energy & CO₂ emissions:

We now present two important benchmarks in respect of Electrical Energy consumption & CO₂ emissions as under.

| No | Particulars | Value | Unit |
|----|-----------------------------|-------|-----------------------|
| 1 | Electrical Energy consumed | 2.44 | kWh/sq. ft. |
| 3 | CO ₂ - Emissions | 1.01 | Kg per annum /sq. ft. |

6. Recommendations:

We present herewith various proposals to reduce the Electrical Energy demand and reduce the CO_2 emissions

| S. No. | Recommendation | Annual saving potential in kWh /Kg of LPG | Annual Saving Potential in MT of CO ₂ | Annual monetary gain, Rs. |
|-----------|--|---|---|---------------------------------|
| 1 | Installation of 50kW Solar PV roof top on college building | 84000 kWh | 67.2 | 840000 |
| 2 | Solar street lights | 262.8 kWh | 0.21 | 2628 |
| 3 | Solar powered light for hoarding | - | - | - |
| 4 | Solar charging stations | - | - | - |
| | Total | 84262.8 | 67.41 | 842628 |

Notes & assumptions:

- 1. 1 Unit of Electrical Energy releases 0.8 Kg of CO₂ into atmosphere
- 2. 1 Kg of LPG releases 3 Kg of CO_2 into atmosphere
- 3. Daily working hours-10
- 4. Annual working Days-280
- 5. Average Rate of Electrical Energy- Rs 10 per kWh

ABBREVIATIONS

| DP | : | Double Pole |
|--------|---|---|
| CFL | : | Compact Fluorescent Lamp |
| EESL | : | Energy Efficiency Services Limited |
| FΡ | : | Feeder Pillar |
| MSEDCL | : | Maharashtra State Electricity Distribution Company Ltd. |
| MEDA | : | Maharashtra Energy Development Agency |
| MIDC | : | Maharashtra Industrial Development Corporation |
| V | : | Voltage |
| I | : | Current |
| kW | : | kilo-Watt |
| kVA | : | Apparent Power |
| kVAr | : | Reactive Power |
| ΡF | : | Power Factor |
| kWp | : | Kilo Watt peak |

CHAPTER-I ENVIRONMENT AND GREEN AUDIT: INTRODUCTION

1.1 Objectives:

- 1. To Study tree plantation in college campus
- 2. To Study the present CO₂ emissions
- 3. To study Scope for usage of Renewable Energy
- 4. To study various measures for sustainable development

1.2 General Details of Bharati Vidyapeeth's College of Engineering, Lavale, Pune:

| No | Head | Particulars | |
|----|-----------------------|---|--|
| 1 | Name of Institution | Bharati Vidyapeeth's College of Engineering | |
| 2 | Address | Lavale, Pune | |
| 3 | Year of Establishment | 2012 | |
| 4 | Salient Features | Affiliated to Savitribai Phule Pune University | |
| 4 | Courses offered | UG in Civil, Computer, E&TC and Mechanical Engineering | |
| 5 | No of Students | 654 | |
| 6 | Total built up area | 173695 Sq. ft. | |

CHAPTER-II GREEN AUDIT FOR AY-2023-24

Bharati Vidyapeeth's College of Engineering, Lavale,, Pune is one of the leading higher technical educational Institutions of Pune under Savitribai Phule Pune University, Pune. It has been providing quality education in Engineering and technical education to the students in various professional courses. The College is having beautiful green campus and a highly greenery maintenance college in Pune. We have prepared a green audit report after visiting the college campus by our team. This green audit report is based on the following major points.

- 1. Plantation in the campus
- 2. Carbon accounting
- 3. Illumination in class rooms
- 4. Water audit and Rainwater Harvesting
- 5. Waste disposal

1. Plantation in the campus

Plantation is playing very important role in the green audit and helping to save environment from damage. The campus plantation is very diverse and well maintained.

The different species are cultivated to increase greenery of the campus. The species included Trees, Shrubs, Herbs, Climbers, ornamentals etc.

There are about 709 big and small trees present inside Bharati Vidyapeeth's College of Engineering, Lavale, Pune campus. After a daylong survey and records about the plantation in the campus is prepared which is as per following table.

| Sr. No. | Name of Tree | Quantity |
|---------|---------------------------|----------|
| 1 | Fox tail palm | 60 |
| 2 | Bakul | 07 |
| 3 | Chata | 179 |
| 4 | Fan Palm | 11 |
| 5 | Revenue Palm | 22 |
| 6 | Arjun | 01 |
| 7 | Sonchata | 05 |
| 8 | Cycus revolata | 14 |
| 9 | Bismark Palm | 08 |
| 10 | Rain tree | 15 |
| 11 | Ficus bengalensis (Vad) | 05 |
| 12 | Jambhul | 02 |
| 13 | Annona squmosa (Sitaphal) | 06 |
| 14 | Mango | 10 |
| 15 | Kadambha | 08 |
| 16 | Pimpale | 02 |
| 17 | Sterculiya | 46 |
| 18 | Shisam | 05 |
| 19 | Adeniya | 21 |
| 20 | Kanchan | 44 |
| 21 | Phonix Palm | 06 |
| 22 | Bamboo Groups | 20 |
| 23 | Aviciniya | 02 |

| 24 | Sphathodiya | 26 |
|----|--------------------------------|-----|
| 25 | Tobu Biya Roseaya | 06 |
| 26 | Ficus Salicifoliya | 26 |
| 27 | Neem Tree | 05 |
| 28 | Cassiya | 07 |
| 29 | Karanj | 23 |
| 30 | Katesawar | 03 |
| 31 | Bilva | 02 |
| 32 | Octopus Tree | 02 |
| 33 | Badam Tree | 02 |
| 34 | Cassiya Fistula (Bava) | 07 |
| 35 | Bhend (Gulbhendi) | 22 |
| 36 | Kejeliya Pinnata (Monkay Tree) | 08 |
| 37 | Tobu Biya | 04 |
| 38 | Parkiya | 24 |
| 39 | Bottle Brush | 04 |
| 40 | Jadropha | 02 |
| 41 | Flaus Spp | 08 |
| 42 | Acasiya | 10 |
| 43 | Kavath | 02 |
| 44 | Cassiya | 03 |
| 45 | Milingtoniya Hortensis (Butch) | 04 |
| 46 | Guava (Pory) | 04 |
| 47 | Bel | 06 |
| | Total | 709 |



Photo-1: Tree plantation of Bharati Vidyapeeth's College of Engineering, Lavale, Pune



Photo-2: Entry view with Tree Plantation at Bharati Vidyapeeth's College of Engineering, Lavale, Pune




Photo-3: Open theater with greenery at Bharati Vidyapeeth's College of Engineering, Lavale, Pune

1.1 Calculation of amount of co₂ sequestered in trees per year

The carbon sequestration potential of the plant species present in green belt has been estimated and suitable plant with maximum sequestration of CO_2 was recommended. Carbon sequestration is nothing but capturing atmospheric carbon dioxide or anthropogenic CO_2 from large scale stationary sources like cement industry before it is released to the atmosphere. Once captured, the CO_2 gas is put into long term storage. CO_2 sequestration in plants has the potential to significantly reduce the level of carbon that occurs in the atmosphere. Terrestrial or biologic sequestration means using plants to capture CO_2 from the atmosphere and then storing it as carbon in the stems and roots of the plants as well as in the soil. The green belts in industrial area acts as sink for capturing and storing carbon dioxide released from the industries.

Assessment of carbon sequestration ability of trees for adopting in greenbelt of cement industries The carbon dioxide sequestered in plant species are determined based on following method:

- 1. Determine the total (green) weight of the tree
- 2. Determine the dry weight of the tree
- 3. Determine the weight of carbon in the tree
- 4. Determine the weight of carbon dioxide sequestered in the tree

5. Determine the weight of CO₂ sequestered in the tree per year

1.2 Determination of Total (Green) Weight of the Tree

The algorithm to calculate the weight of a tree is:

For trees with D < 11: W = $0.25D^2H$

For trees with $D \ge 11$: $W = 0.15D^2H$

Where, W = Above-ground weight of the tree in pounds

D = Diameter of the trunk in inches

H = Height of the tree in feet

Depending on the species, the coefficient (e.g. 0.25) could change and the variables D^2 and H could be raised to exponents just above or below 1. However, these two equations could be seen as an "average" of all the species' equations. The root system weighs about 20% as much as the above-ground weight of the tree. Therefore, to determine the total green weight of the tree, multiply the above-ground weight of the tree by 120%.

1.3 Determination of Dry Weight of the Tree

Taking all species in into account, the average tree is 72.5% dry matter and 27.5% moisture. Therefore, to determine the dry weight of the tree, multiply the weight of the tree by 72.5%.

1.4 Determine the weight of carbon in the tree

The average carbon content is generally 50% of the tree's total volume. Therefore, to determine the weight of carbon in the tree, multiply the dry weight of the tree by 50%.

Assessment of carbon sequestration ability of trees for adopting in greenbelt of cement industries Determine the weight of carbon dioxide sequestered in the tree

CO₂ is composed of one molecule of Carbon and 2 molecules of Oxygen.

The atomic weight of Carbon is 12.001115.

The atomic weight of Oxygen is 15.9994.

The weight of CO_2 is C+2*O=43.999915.

The ratio of CO₂ to C is 43.999915/12.001115=3.6663.

Therefore, to determine the weight of carbon dioxide sequestered in the tree, multiply the weight of carbon in the tree by 3.6663

Determine the weight of CO₂ sequestered in the tree per year

Divided the weight of carbon dioxide sequestered in the tree by the age of the tree.

2. Carbon Accounting

A Carbon Foot print is defined as the Total Greenhouse Gas emissions, emitted due to various activities.

In this we compute the emissions of Carbon-Di-Oxide, by usage of the various forms of Energy used by the College for performing its day to day activities. The college uses electrical energy for operating various electrical gadgets.

We herewith furnish the details of electrical Energy consumption consumer number wise as under

| Sr. No | Month | kVAh |
|--------|------------|----------|
| 1 | Nov-2023 | 14785 |
| 2 | Oct-2023 | 20795 |
| 3 | Sep-2023 | 18412 |
| 4 | Aug-2023 | 15822 |
| 5 | July-2023 | 14403 |
| 6 | June-2023 | 21338 |
| 7 | May-2023 | 26246 |
| 8 | April-2023 | 20323 |
| 9 | March-2023 | 19238 |
| 10 | Feb-2023 | 15298 |
| 11 | Jan-2023 | 16631 |
| 12 | Dec-2022 | 18077 |
| 13 | Total | 221368 |
| 14 | Average | 18447.33 |
| 15 | Max | 26246 |
| 16 | Min | 14403 |

4.1 Month wise Consumption of Electrical Energy: 182829055190

4.2 Basis for computation of CO₂ Emissions:


The basis of Calculation for CO₂ emissions due to Electrical Energy are as under

• 1 Unit (kWh) of Electrical Energy releases 0.8 Kg of CO2 into atmosphere

Based on the above Data we compute the CO_2 emissions which are being released in to the atmosphere by the College due to its Day to Day operations.

4.3 Month wise CO2 Emissions: 182829055190

| Sr. No | Month | Electrical Energy Consumed, kVAh | CO2 Emissions due to Electricity, MT |
|--------|------------|-------------------------------------|---|
| 1 | Nov-2023 | 14785 | 11.83 |
| 2 | Oct-2023 | 20795 | 16.64 |
| 3 | Sep-2023 | 18412 | 14.73 |
| 4 | Aug-2023 | 15822 | 12.66 |
| 5 | July-2023 | 14403 | 11.52 |
| 6 | June-2023 | 21338 | 17.07 |
| 7 | May-2023 | 26246 | 21.00 |
| 8 | April-2023 | 20323 | 16.26 |
| 9 | March-2023 | 19238 | 15.39 |
| 10 | Feb-2023 | 15298 | 12.24 |
| 11 | Jan-2023 | 16631 | 13.30 |
| 12 | Dec-2022 | 18077 | 14.46 |
| 13 | Total | 221368 | 177.09 |
| 14 | Average | 18447.33 | 14.76 |
| 15 | Max | 26246 | 21.00 |
| 16 | Min | 14403 | 11.52 |



4.4 Representation of Month wise CO₂ emissions:

4.5 Benchmarking:

Now we compute the CO2 emissions per sq. ft. basis as under:

| No | Parameter | Value | Unit |
|----|-----------------------|--------|--------------------------------|
| 1 | CO2 emissions | 177.09 | MT/annum |
| 2 | College area | 173695 | Sq. ft. |
| 3 | CO2 emissions/sq. ft. | 1.01 | Kg of CO₂ per annum/sq. ft. |

3. Use of Renewable energy options for saving the environment

3.1 Installation of 50 kWp Solar PV roof Top on Bharati Vidyapeeth's College of Engineering, Lavale building:

During the Audit, it was revealed that the College has ample space on the Terrace but top two floors under construction. It is proposed once construction completes Solar Photovoltaic roof top with net meter of capacity **50 kWp can be installed.** The system will cater the Day load Demand of the College.

| No | Particulars | Value | Unit |
|----|---|----------|-------------|
| 1 | Installed Capacity of Solar PV Pack | 50 | kWp |
| 2 | Daily working period | 6 | Hrs./Day |
| 3 | Daily units generated | 300 | kWh/Day |
| 4 | Annual working days | 280 | Day/annum |
| 5 | Annual saving in Grid Electrical Energy | 84000 | kWh/annum |
| 6 | Annual CO ₂ saving potential | 67.2 | MT/Annum |
| 7 | Present Energy Charges | 10 | Rs/kWh |
| 8 | Annual monetary Gain | 840000 | Rs/Annum |
| 9 | Investment required | 22,50000 | Rs lump sum |
| 10 | Payback period | 2.67 | Years |

We furnish herewith the saving potential as under

3.2 Solar Water heater

Today we are facing the shortage problem between supply and demand of electric energy especially during peak summer and winter seasons. The situation further worsens during early hours of peak winter season when enormous heating load is switched 'ON'. This has been a consistent problem. If the heating load is switched over to non-conventional source of energy, from conventional energy sources, the gap can be bridged considerably. 'Solar Energy' is an unlimited source of non-conventional energy. Solar energy can provide cost-effective solutions to fight climate change and reduce our dependency on expensive and polluting fuels. A solar water heater is an efficient and reliable technology that converts sunlight into heat to produce your hot water. At present Bharati Vidyapeeth's College of Engineering, Lavale campus uses electric gysers in 24 nos. having capacity of 15 litrs and 3 kW coil for hot water production in boys hostel.



Photo-4: Electric geysers at Bharati Vidyapeeth's College of Engineering, Lavale, Pune

Solar water heating system of total capacity of 1000 LPD can be used to provide hot water for bathing purpose for students, which will decrease the electrical energy consumption.

3.3 Solar powered light for hoarding

Lighting solar systems are the fixed installations designed for domestic as well as small scale commercial application. The component of the solar lighting system includes solar PV module (solar cells), charge controller, solar battery and lighting system (lamps & fans). Modules are installed in the open on roof/terrace - exposed to sunlight and the charge controller and battery are kept inside a protected place in the house.



Figure-1: Solar powered light for Hoarding

This system comes with multiple benefits such as:

- **Economical:** Since the sun provides energy free of charge, 30% power savings on the electricity bill can be availed with longer back up lighting system at zero running cost.
- **Non-Polluting:** Powered by the sun's renewable energy, the system is energy neutral and an absolutely clean source of illumination. 1kWp solar installation reduces 1/2 ton of CO₂ (carbon dioxide) per annum.
- **No Maintenance:** The system has few moveable parts reducing the risk of breakage. Once installed, it lasts for long time and requires little attention.

This system can be used to power the huge hoardings in the college campus.

Solar powered hoarding lighting system proposed will provide a better, faster, cheaper (and cleaner) alternative with solar. Since this product competes with diesel or conventional fuels, we needed to ensure we beat the cost of a diesel solution. In order to achieve that with solar, we consider the following system:

1. Highly Efficient Solar Panel

2. Charge Controllers with MPPT Technology – increases solar electricity production by up to 30% compared to conventional charge controllers

3. LED Projection Light – consumes 10-times less electricity compared to conventional bulbs, and has a 50,000 hour warranty.

Features:


Auto on off


- 4 Days Battery Back Up
- Robust housing
- Weather proof

With this entire put together, we ended up with systems that provide 6 hours of lighting each night with 4 -lamp system to light up boards up to 15'x30', and a 8-lamp system to light larger boards up to 20'x40'. More importantly, with these options, payback of the system will come around 2.5 years. This system provides a way to reduce the lightings costs, get rid of all the operational hassles of owning a diesel generator, plus brand benefits from being "green" with the use of renewable energy like solar powered light hoarding board.

3.4 Solar charging stations

Solar cell phone chargers use solar panels to charge cell phone batteries. They are an alternative to conventional electrical cell phone chargers and in some cases can be plugged into an electrical outlet. Solar mobile charger is a device which can charge mobile phones using solar radiation. Its major component is a compact solar panel. This solar panel traps solar energy and produces an output voltage. But, since the light radiations falling on the solar panel can vary, the output voltage becomes unstable. For charging a mobile phone, stable voltage is required. So, to make the output voltage stable and regulated, voltage regulator circuit along with the solar panel is used.





Most of the mobile phones have computer connectivity via USB cable. USB port establishes 4 connection terminals. The connection terminals at the two extreme ends are the supply terminals. In a female USB connector (port via which we plug in USB devices to computer), these terminals carry 5V DC. When a mobile phone is connected to the USB port of a computer, it utilizes this 5V supply to recharge battery. This feature is used in a solar mobile charger. It converts and regulates solar energy to 5V DC and the output will be available through the female USB connector. To this connector, we can easily connect a mobile phone via data cable.

4. Illumination in class rooms

Lighting puts a huge impact on the visibility and appearance of every space. Sufficient and beautiful lighting can enhance the look of a dull space, whereas improper lighting implementations can make a catchy area look less impressive. Poor lighting at work can lead to eye-strain, fatigue, headaches, stress and accidents. On the other hand, too much light can also cause safety and health problems such as "glare" headaches and stress. Bharati Vidyapeeth's College of Engineering is using daylight effectively, specifically at corridors. The typical class room illumination in lux is mentioned as below.




Figure 3: Chemistry Lab Lower Ground Floor






Figure 4: Central Library Lower Ground Floor





5. Water Audit and Rain water harvesting

A water crisis is a very sensitive issue these days all over the world. Recently we are facing water crisis in major part of Maharashtra like Marathwada, Khandesh, Pachim Maharashtra and North Maharashtra. Bharati Vidyapeeth's College of Engineering, Lavale, Pune has taken a good initiative for maintaining greenery in the campus and less concrete zone, it means that college campus is allowing the rainwater to absorb under the ground and maintain the underground water level. In addition to this as per the survey and site location following activities can be implemented for the conservation of water.

5.1 Water storage and consumption

Bharati Vidyapeeth's College of Engineering, Lavale, campus is having water supply from the well to mitigate the need of requirement water for various activities. The college campus has temporary water storage capacities in terms of overhead tanks on the Institute building. Water is temporarily stored in the campus for various activities. There is a provision of sparkler system to supply the water in garden to maintain greenery. The details of water storage in the campus as mentioned below.


| Tank type | For Regular Use (Itr) | Quantity |
|---------------------------------|--------------------------|----------|
| For regular Use in the building | 3,57,000 | 01 |

5.2. Rain water harvesting

The system of rain water harvesting is an integral part of any educational institution. This system helps to conserve the rain water and also to use during the time of its desirable. This system helps the students to understand the basic concepts of rainwater harvesting system and their effective use in the real life.

Already Bharati Vidyapeeth's College of Engineering, Lavale, Pune have provisions of collection of gray waste water from all the building taken through some specific path and charged in the ground below building to maintain the ground level water. It is suggested to charge the rain water through ring well in the campus.





Advantages of rain water harvesting

- (a) Promotes adequacy of underground water
- (b) Mitigates the effect of drought
- (c) Reduces soil erosion as surface run-off is reduced
- (d) Decreases load on storm water disposal system
- (e) Reduces flood hazards
- (f) Improves ground water quality / decreases salinity

(by dilution)

- (g) Prevents ingress of sea water in subsurface aquifers in coastal areas
- (h) Improves ground water table, thus saving energy (to lift water)
- (i) The cost of recharging subsurface aquifer is lower than surface reservoirs
- (j) The subsurface aquifer also serves as storage and distribution system
- (k) No land is wasted for storage purpose and no population displacement is involved
- (I) Storing water underground is environment friendly.

Rain water harvesting potential

The total amount of water that is received in the form of rainfall over an area is called the rain water endowment of that area. Out of this, the amount that can be effectively harvested is called rain water harvesting potential.

All the water which is falling over an area cannot be effectively harvested, due to various losses on account of evaporation, spillage etc. Because of these factors the quantity of rain water which can effectively be harvested is always less than the rain water endowment. The collection efficiency is mainly dependent on factors like runoff coefficient and first flush wastage etc. Runoff is the term applied to the water that flows away from catchments after falling on its surface in the form of rain.

Runoff depends upon the area and type of catchment over which it falls as well as surface features. Runoff can be generated from both paved and unpaved catchment areas. Paved surfaces have a greater capacity of retaining water on the surface and runoff from unpaved surface is less in comparison to paved surface. In all calculations for runoff estimation, runoff coefficient is used to account for losses due to spillage, leakage, infiltrations catchment surface wetting and evaporation, which will ultimately result into reduced runoff. Runoff coefficient for any catchment is the ratio of the volume of water that run off a surface to the total volume of rainfall on the surface. The runoff coefficient for various surfaces is given in following table

| Sr. | Type of catchment | Coefficient |
|-----|------------------------------|-------------|
| No. | | |
| 1 | Roof Catchments | |
| | Tiles | 0.8-0.9 |
| | Corrugated metal sheets | 0.7-0.9 |
| 2 | Ground surface coverings | |
| | Concrete | 0.6-0.8 |
| | Brick pavement | 0.5-0.6 |
| 3 | Untreated ground catchments | |
| | Soil on slopes less than 10% | 0.0-0.3 |
| | Rocky natural catchments | 0.2-0.5 |

Based on the above factors, the water harvesting potential of site could be estimated using the following equation:

Rain Water harvesting potential = Amount of Rainfall x area of catchment x Runoff coefficient

Rain water harvesting methods


- (a) Storing rain water for direct use
- (b) Recharging ground water aquifers, from roof top run off
- (c) Recharging ground water aquifers with runoff from ground area

According to the site of Bharati Vidyapeeth's College of Engineering, Lavale, Pune campus the method of recharging ground water aquifiers from roof top run off may be suitable.

Recharging ground water aquifers from roof top run off

Rain water that is collected on the roof top of the building may be diverted by drain pipes to a filtration tank (for bore well, through settlement tank) from which it flows into

the recharge well, as shown in following Figure. The recharge well should preferably be shallower than the water table. This method of rain water harvesting is preferable in the areas where the rainfall occurs only for a short period in a year and water table is at a shallow depth. The schematic diagram of recharging water aquifers from roof top run off is as follows.



RECHARGE THROUGH INJECTION (BORE) WELL

6. Waste disposal

The present Prime Minister of India, Shri Narendra Modiji launched "Swach Bharat Abhiyan" (Clean India Mission), on 2nd October, 2014. In this mission, the proper use of dustbins is one of the major priorities. For the successful implementation of this mission collective mass effort is necessary. The higher education institutions like Bharati Vidyapeeth's College of Engineering, Lavale, Pune need to play a major role in this regard to keep their campus neat and clean. Proper use of dustbins is not only the solution for the generating garbage in the college campus. Now days, its proper treatment should be given a major priority.

| Sr. No. | Waste Category | Method of disposal |
|---------|--|--|
| 1 | Solid waste from trees droppings and lawn | Vermi Composting Organic Manure |
| 2 | Canteen waste | Vermi Composting Organic Manure |
| 3 | Plastic waste | Through Authorized recycler after segregation |
| 4 | Chemical waste generated in chemistry | The college need to have a very good practice to use dilute chemicals for the experimentation in these labs. These dilute chemicals can be further diluted and disposed in the pit near the lab. |
| 6 | E-waste and defective items from computer and electronics lab | The institution collects e-waste and delivered to authorized agency in order to dispose E-waste in scientific manner. |
| 7 | Sanitary Napkins | The institution have to take a very good initiative to install sanitary napkin disposal machine at the different location in the college campus. It is suggested to install vending machine along with incinerators at required locations in the college campus. |

Characteristic and Disposal Practices of Solid Wastes Waste Management

6.1 Vermiculture Composting Culture

Vermicomposting is basically a managed process of worms digesting organic matter to transform the material into a beneficial soil amendment. The main purpose of this is to reduce disposable waste in the college campus and after complete process of vermi composting it is used as manure for plantation and greenery in the campus. It is also used for the demonstration and awareness in farmers to implement organic farming and its importance.

The main benefits of the process are to reduce the waste in the environment and utilized for some useful purpose and also it is cost savings process.

The earthworms being voracious eaters consume the biodegradable matter and give out a part of the matter as excreta or vermi-castings. The vermi-casting containing nutrients is a rich manure for the plants. Vermicompost, apart from supplying nutrients and growth enhancing hormones to plants, improves the soil structure leading to increase in water and nutrient holding capacities of soil. Fruits, flowers and vegetables and other plant products grown using vermicompost are reported to have better keeping quality. A growing number of individuals and institutions are taking interest in the production of vermicompost utilizing earthworm activity. As the operational cost of production of this compost works out to less than `Rs. 2.0/Kg., it is quite profitable to sell the compost even at Rs. 4.00 to 4.50/Kg.

Process:

The process of composting crop residues / agri wastes using earthworms comprise spreading the agricultural wastes and cow dung in gradually built up shallow layers. The pits are kept shallow to avoid heat built-up that could kill earthworms. To enable earthworms to transform the material relatively faster a temperature of around 30°C is maintained. The final product generated by this process is called vermicompost which essentially consist of the casts made by earthworms eating the raw organic materials. The process consists of constructing brick lined beds generally of 0.9 to 1.5 m width and 0.25 to 0.3 m height are constructed inside a shed open from all sides. For commercial production, the beds can be prepared with 15 m length, 1.5 m width and 0.6 m height spread equally below and above the ground. While the length of the beds can be made as per convenience, the width and height cannot be increased as an increased width affects the ease of operation and an increased height on conversion rate due to heat built up.

Cow dung and farm waste can be placed in layers to make a heap of about 0.6 to 0.9 m height. Earthworms are introduced in between the layers @ 350 worms per m3 of bed volume that weighs nearly 1 Kg. The beds are maintained at about 40-50% moisture content and a temperature of $20-30^{\circ}$ C by sprinkling water over the beds. When the commercial scale production is aimed at, in addition to the cost of production, considerable amount has to be invested initially on capital items. The capital cost may work out to about Rs. 5000 to 6000 for every tonne of vermicompost production capacity. The high unit capital cost is due to the fact that large units require considerable expenditure on preparation of vermi beds, shed to provide shelter to these beds and machinery. However these expenditures are incurred only once.

Under the operational cost, transportation of raw materials as also the finished product are the key activities. When the source organic wastes and dung are away from the production facility and the finished product requires transportation to far off places before being marketed, the operational cost would increase. However, in most of the cases, the activity is viable and bankable. Following are the items required to be considered while setting up a unit for production of vermi-compost.

Components of a Commercial Unit

Commercial units have to be developed based on availability of cow dung locally. If some big dairy is functioning then such unit will be an associated activity. Commercial units must not be designed based on imported cow dung.

1. Sheds

For a vermi-composting unit, whether small or big, this is an essential item and is required for securing the vermi beds. They could be of attached roof supported by bamboo rafters or steel trusses. Locally available roofing materials or HDPE sheet may also be used in roofing to keep the capital investment at reasonably lower level. If the size is so chosen as to prevent wetting of beds due to rain on a windy day, they could be open sheds. While designing the sheds

adequate room/pathways has to be left around the beds for easy movement of the labourers attending to the filling and harvesting the beds.

2. Vermi-beds

Normally the beds have 0.3 to 0.6 m height depending on the provision for drainage of excess water. Care should be taken to make the bed with uniform height over the entire width to avoid low production owing to low bed volumes. The bed width should not be more than 1.5 m to allow easy access to the center of the bed.

3. Fencing and Roads/Paths

The site area needs development for construction of structures and development of roads and pathways for easy movement of hand-drawn trolleys/wheel barrows for conveying the raw material and the finished products to and from the vermi-sheds. The entire area has to be fenced to prevent trespass by animals and other unwanted elements. These could be estimated based on the length of the periphery of the farm and the length and type of roads/paths required. The costs on fencing and formation of roads should be kept low as these investments are essential for a production unit, yet would not lead to increase in production.

4. Water Supply System

As the beds have to be kept moist always with about 50% moisture content, there is a need to plan for a water source, lifting mechanism and a system of conveying and applying the water to the vermi-beds. Drippers with round the clock flow arrangement would be quite handy for continuous supply and saving on water. Such a water supply system requires considerable initial investment. However, it reduces the operational cost on hand watering and proves economical in the long run. The cost of these items would depend on the capacity of the unit and the type of water supply chosen.

5. Transportation

For any vermi-composting unit transport arrangement is a must. When the source of raw material is away from the production unit, an off-site transport becomes major item of investment. A large sized unit with about 1000 tonnes per annum capacity may require a three tonne capacity mini-truck. With small units particularly with the availability of raw material near the site, expending on transport facility may become infructuous. On-site transport facilities like manually drawn trolleys to convey raw material and finished products between the storage point and the vermi-compost sheds could also be included in the project cost.

Design calculations

The size of the bed can selected as per the space available and convenient to the customer. Brick lined beds generally of 0.9 to 1.5 m width and 0.25 to 0.3 m height are constructed inside a shed open from all sides. On the basis of site survey and suitability of operation lets consider following dimensions for the bed. Generally, earthworms are introduced in between the layers @ 350 worms per m3 of bed volume that weighs nearly 1 Kg.

L= 3 m W = 1.5 m H = 0.6 m Volume of the bed = 2.7 m³ $Input = \frac{15 \, kg \, of \, organic residue}{m3 \times 15 \, days} = \frac{1 \, kg \, of \, organic residue}{m3 \times 1 \, day}$

It means for 2.7 m³, 270 kg of organic residue is required. Therefor for a month approximately 8100 kg (8.1 Ton) of organic residue is required.

The financial viability on the basis of available data of the vermicompost system is shown below.

| Sr. No. | Particulars | Expenditure Cost |
|---------|-------------------------------|-------------------|
| | | (Rs.) |
| 1 | Bed construction | Already available |
| | | 10,000/- |
| 2 | Fencing including roof | 5000/- |
| 3 | Water Dripper | 3000/- |
| 4 | Electrical connections | 1000/- |
| 5 | Earthworms | 1000/- |
| 6 | Salary & wages | 20000/- |
| 7 | Sale of Vermicompost (@ | 121500/- |
| | Rs.100 /kg at 30% conversion) | |
| | Net Benefit | 81500/- |



Photo-6: Beds for Vermi-compost at college campus

Chapter III SUGGESTIONS AND RECOMMENDATIONS

Following are the suggestions and actions on the basis of green and environmental audit are suggested to implement in the campus on the basis of funds availability and institute preferences.

Green Audit: Environment conservation opportunities:

- Plants/Trees in the college campus may be designated with botanical name and specific number on the basis of year of plantation. There will be brick arrangement at the bottom to supply water to the plant.
- Water management system must be in place. Reduction in water consumption by addressing leakages of taps and other miscellaneous utilities. Installation of flow meters which will help in reduction of water consumption. TOD can be implemented for water pumping application.
- Rainwater harvesting pipe which collects rain water from respective building may have filter and properly charge the ground through ring well.
- > Provide required nos. of dustbins at respective locations in the college campus.
- Vermi-culture composting plant should be in working condition and the organic compost from the same will be either utilized for the plants/trees and maintaining greenery in the college campus or sell for organic farming.
- It is suggested to display Energy conservation slogans boards in the college campus and classroom to make awareness about importance of energy saving.

Prathamesh Energy Solution

A-302, Shiv Unnati Residency, Kalepadal, Hadapsar, Pune-411028

Invoice No. PES/BVCOEL/23-24

Date: 07/02/2024

Ref: BV/COEL/85/2023-24, Dated 27/12/2023

To,

The Principal Bharati Vidyapeeth College of Engineering, Lavale, Pune

| Sr. No. | Description | Amount |
|------------|--|-------------------------------------|
| 1. | Detailed Energy and Environmental/Green Audit as per following scope of work | 65,000/- |
| | Study of connected load | |
| | Measurement of V, I, PF, kW and kVA etc | |
| | Study of lighting | |
| | Study of other Utilities in the facility | |
| | Preparation of report and submission to the MEDA and Institute | |
| | Green and environment audit on the basis of data submitted and survey of the site. | |
| | Total | 65,000/- |
| | Amount in Words | Sixty Five Thousand Rupees only. |
| | Note: Invoice is raised as per the PO received (BV/COEL/85/2023-24, Dated 27/1 | |

Account Details

Bank: Bank of Baroda

Branch Address: Saswad Road, Hadapsar, Pune

Account No.: 2483020000990 IFSC:BARB0HADAPS (Fifth Character is Zero) PAN: BJKPR4759K For Prathamesh Energy Solution

Jandome

Authorized Signatory





सावित्रीबाई फुले पुणे विद्यापीठ राष्ट्रीय सेवा योजना Academic Year 2023-2024

Bharati Engineering College of Engineering, Lavale, Pune

HAVE ORGANIZED

Swachh Bharat




DATE - 28/10/23

Program Officer PROF. S.C.PATIL

a.

DR. R.N.PATIL

Principal



SHARAT DYAPEETH.

Founder: **Dr. Patangrao Kadam** M.A., L.L.B., Ph.D.

BHARATI VIDYAPEETH'S COLLEGE OF ENGINEEERING, LAVALE, PUNE 412 115.

Recognized by AICTE, New Delhi & DTE Mumbai. Affiliated to Savitribai Phule Pune University.

Ref. No.BV/COEL/

2.

/2023-2024

Date: 27 / 10 2023

NATIONAL SERVICE SCHEME


NOTICE

All students are hereby informed that we are conducting "Swachh Bharat Mission 3.0" on our campus on the date of 28.10.2023.

01. Swachh Bharat Mission BVCOEL Campus on 28.10.2023

02. Swachh Bharat Mission at Lavale on 28.10.2023

Scan QR Code & Fill in form to register for the participation.



Note: Participation certificate will only be issued to registered students.

PROGRA M OFFICER (PO)

Bha ar which College of Eron Stavels, Pune

Principa

2.

Q. .

Website: <u>http://bvcoe.bharatividyapeeth.edu/index.php</u> Email: <u>coelpune@bharatividyapeeth.edu</u>



D. .





सावित्रीबाई फुले पुणे विद्यापीठ पुणे

NATIONAL SERVICE SCHEME

Name of College: Bharati Vidyapeeths's College of Engineering, Lavale, Pune -412115

| | NSS Code | A-SF-147 |
|-----|-------------------------|----------------------------|
| 01. | Name of Program | Swachh Bharat Mission |
| | Name of Program Officer | Prof. S.C. Patil |
| 03. | Date and Time | 28-10-2023 Monday, 10:30AM |
| 04. | Participant Male | 40 |
| 05. | Participant Female | 20 |
| | Total Beneficiaries | 75 |

Name of Report on: Swachh Bharat Mission

Bharati Vidyapeeth's College of Engineering. Lavale. Pune, conducting workshop by Prime Minister Shri Narendra Modi launch 'Swachh Bharat Mission 'on 28th October, 2023 at 10:30 AM. Prime Minister addressed the Vice Chancellors of the Universities. Heads of Institutes and faculty members in workshops organized at Raj Bhawans across the country, which symbolize the start of the initiative.

Prime Ministers vision is to actively involve the youth of the count in formulation of national plans, priorities and goals of the country. World Swachh Bharat Mission Day is celebrated annually on October 28th to raise awareness and encourage global action for the protection of the environment. It serves as a platform for individuals, communities, and governments to come together and take positive steps towards sustainable practices.

The day focuses on a different environmental theme each year, addressing issues such as climate change, biodiversity, pollution, and sustainable development. It's a great opportunity for people to reflect on their impact on the environment and consider ways to reduce their ecological footprint.

2.







2.

सावित्रीबाई फुले पुणे विद्यापीठ पुणे NATIONAL SERVICE SCHEME

Name of College: Bharati Vidyapeeths's College of Engineering, Lavale, Pune -412115

Name of Report on: Swachh Bharat Mission

Photo Gallery:



Photo No. 01 with all students

2.



Photo No. 02 with all students

Program Officer

Programme Officer Bharab VA to speeth College of Engineering Lavais, Pune NSS, SEPU



Dr. R. N. Patil I/C PRINCIPAL BHARATI VID VAPUE FH COLLEGE OF ENGINEERING, LAVALE Tal-Mulshi, Dist, Pun



सावित्रीबाई फुले पुणे विद्यापीठ

राष्ट्रीय सेवा योजना NSS UNIT CODE A-SF-147

Academic Year 2023-2024

Bharati Engineering College Of engineering, Lavale, Pune HAVE ORGANIZED

• TREE PLANTATION DATE - 03/07/23

Program Officer PROF. S.C.PATIL

Principal DR. R.N.PATIL

Venue - Bharati Engineering College Of Engineering, Lavale, Pune







सावित्रीबाई फुले पुणे विद्यापीठ पणे

NATIONAL SERVICE SCHEME

Name of College: Bharati Vidyapeeths's College of Engineering, Lavale, Pune -412115

Name of Report on: Tree Plantation

| | NSS Code | A-SF-147 |
|-----|-------------------------|------------------|
| 01. | Name of Program | Tree Plantation |
| 02. | Name of Program Officer | Prof. S.C. Patil |
| 03. | Date and Time | 03-07-2023 |
| 04. | Participant Male | 45 |
| 05. | Participant Female | 32 |
| 06. | Total Tree plantation | 75 |

Topic: Tree Plantation Coordinator: Prof. S. C . Patil Location: Bharati Vidyapeeths College of Engineering Lavale, Pune.

Introduction: The Tree Plantation program, under the supervision of Prof. S.C. Patil, was organized on 04/03/2024 at Bharati Vidyapeeth's College of Engineering Lavale, Pune. This initiative coincided with the Azadi Ka Amrit Mahotsav, and it aimed to instill the importance of tree plantation among participants.

Program Details: The event was attended by a total of 77 participants, with 45male and 32 female individuals taking part in the tree plantation drive. A total of 75 trees were planted during the program, symbolizing a commitment towards environmental sustainability and conservation.

Program Overview:

The Tree Plantation program, spearheaded by Prof. S.C. Patil, was a resounding success. Through collaborative efforts and community engagement, the event succeeded in raising awareness about the importance of tree plantation in fostering sustainable development. The organizers extend their gratitude to all participants for their enthusiastic participation and commitment to environmental conservation.

Recommendations: Moving forward, it is recommended to organize similar tree plantation drives periodically to further reinforce the message of environmental responsibility and encourage active participation from the community.

Acknowledgment: Special thanks to Principal Dr. R. N. Patil Sir for his exemplary leadership and guidance in orchestrating a successful tree plantation program. The support from the organizing committee and participants is also greatly appreciated.








सावित्रीबाई फुले पुणे विद्यापीठ पुणे

NATIONAL SERVICE SCHEME

Name of College: Bharati Vidyapeeths's College of Engineering, Lavale, Pune -412115


Name of Report on: Tree Plantation

Photo Gallery:



Q.

2



Program Officer

Programme Ufficar Bharan A. A Roseth College of Englieeurg Lavele, Pube

æ., .

Principal Dr. R. N. Paul

101 ANCIPAL Tri-Malshi, Nia, Par